

PURCHASE REQUEST


Province of Bohol


Department:
Office of the Provincial Agriculturist
Division: Crops Division
Section: Facility Section


PR No. _____ Date June 24, 2020
SAI No. _____ Date: _____
OB R No. _____ Date: _____

Item No.	Quantity	Unit of Issue	Item Description	Estimated Unit Cost	Estimated Total Cost
Nursery Establishment/Balilihan, Bohol					
I. Insect/Mosquito protection					
1.	15	Meter	Fiber mosquito screen – black 3 ft. width	P 115.00	P 1,725.00
2.	30	Pcs.	Lattice wood (1/2" x 1 1/2" x 8')	101.20	3,036.00
II. Comfort Rooms tile height is 1.2m					
3.	1	Piece	Toilet Bowl (white)	1,380.00	1,380.00
4.	2	Piece	Ceramic lavatory wash basin white	2,760.00	5,520.00
5.	180	Piece	Floor tiles (6"x6") off white color	13.80	2,484.00
6.	536	Piece	Wall tiles (6"x6") off white color	16.10	8,629.60
7.	2	Pack	Tile adhesive (25 kg pack)	324.30	648.60
8.	21	Kg.	Tile grout	40.25	845.25
9.	4	Piece	PVC Tile Trim (8' length)	172.50	690.00
10.	2	Piece	III. Stainless Shower & Faucet 1/2" diam.	1,035.00	2,070.00
11.	2	Piece	PVC 1/2" diam. Pipe x 10'	69.00	138.00
12.	4	Piece	PVC 1/2" diam. Elbow 90 deg.	5.18	20.72
13.	2	Piece	PVC 1/2" diam. T-connection	8.05	16.10
14.	2	Piece	PVC 1/2" diam. Coupling	3.45	6.90
IV. Drainage (Toilet)					
15.	2	Piece	Stainless Floor drain with screen (4"x4")	230.00	460.00
V. Doors and Windows					
16.	3	Piece	3/16"x4"x8' Marine plywood	552.00	1,656.00
17.	24	Bd.ft.	2"x3"x8' Gemilina lumber	74.75	1,794.00
18.	13	Bd.ft.	2"x2"x8' Gemilina lumber	74.75	971.75
19.	0.25	Kg.	CWN # 3	84.00	21.00
20.	0.5	Kg.	CWN # 2 1/2"	80.00	40.00
21.	0.25	Kg.	Finishing nails	80.00	20.00
22.	3	Pair	Butt hinges 3-1/2" x 3-1/2"	138.00	414.00
23.	4	Set	Door Knob	920.00	3,680.00
24.	2	Piece	PVC Door Panel 70cmx210cm	1,840.00	3,680.00
25.	12.4	Sq.m.	Glass jalousie with frame (clear glass)	1,664.70	20,642.28
26.	26	Pieces	Square bar 10mm	281.75	7,325.50
27.	12	Pieces	Angle bar 2.5mm x 1"	437.00	5,244.00
28.	15	Kg.	Welding rod	142.50	2,137.50
29.	112	Pieces	1 1/2" Screw w/ tox	1.73	193.76
30.	1	Piece	Paint brush 1"	40.00	40.00
31.	0.5	Gallon	Primer Paint	340.00	170.00
VI. Electrical supplies					
32.	20	Meter	Twisted service drop wire	29.90	598.00
33.	1	Piece	Medium size strength insulator	200.00	200.00
34.	1	Piece	Service entrance cap 3/4"	50.00	50.00
35.	1	Length	PVC (arrange) pipe 3/4"	190.00	190.00
36.	1	Piece	Panel board 6 branches	1,700.00	1,700.00
37.	1	Piece	Plug-in Breaker 30 A	350.00	350.00
38.	1	Piece	Plug-in Breaker 15 A	350.00	350.00
39.	400	Meter	TTHN wire # 14	18.40	7,360.00
40.	7	Piece	Wall socket (4")	40.00	280.00
41.	7	Piece	CFL bulb 18 watts	230.00	1,610.00
SUB TOTAL A					

BY AUTHORITY OF THE GOVERNOR

Requested by: 
Signature Printed Name: **LARRY M. PAMUGAS, Ph.D.**

Cash Availability: 
EUSTAQUIO A. SOCORIN

Approved by: 
ATTY. KATHYRN P. PIOQUINT
PROVINCIAL ADMINISTRATOR
ATTY. ARTHUR C. YAP
Governor