

Form Number: SF-GOOD-59
 Issued on: May 24, 2004
 Standard Form Title: Purchase Request

PURCHASE REQUEST
OFFICE OF THE SANGGUNIANG PANLALAWIGAN
 Agency/Procuring Entity

Department: Office of the Vice Governor PR No. _____ Date: August 11, 2020

Section: _____ SAI No. _____ Date: _____

STOCK NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT COST	TOTAL COST
	1. 5.0 TR, SLIM TYPE FLOOR MOUNTED PACKAGE A/C	1	set	142,800.00	142,800.00
	5.0 TR, Cooling Capacity, of 60,000 Btu/hr., floor mounted, charged with ozone-friendly refrigerant (R410A), equipped with high AION Air Filter Net that filter that filters out germs, bacteria and allergens, equipped with 12-hr. OFF timer, equipped with the following safety devices so as to protect the unit from total damage: compressor overcurrent relay, compressor discharge thermostat, high pressure switch, reverse phase protection relay, fuse for control circuit and fuse for outdoor unit fan motor; Compressor Warranty: 2 yrs., other parts: 1 year.				
	INSTALLATION MATERIALS, EQUIPMENT SUPPORT, DRAINS, CIRCUIT BREAKERS, WIRES, TAPES & ACCESSORIES:				
	Service Circuit Breaker, 60A, 3Ph, 60hz	1	pc.	1,800.00	1,800.00
	# 08 AWG THHN PHILFLEX	6	mts.	65.00	390.00
	# 12 AWG THHN PHILFLEX	24	mts.	45.00	1,080.00
	PVC Electrical Pipe, orange, 3/4"	5	lengths	150.00	750.00
	PVC Elbow, orange, 3/4"	4	pcs.	45.00	180.00
	PVC Pipe, blue, 1"	4	lengths	165.00	660.00
	PVC Elbow, blue, 1"	4	pcs.	25.00	100.00
	Expansion Shield with lag screw	8	sets	90.00	720.00
	Silver Rod	2	pcs.	85.00	170.00
	Welding Rod	75	pcs.	8.00	600.00
	Bolts, nuts and washers	4	pcs.	15.00	60.00
	Angular Bar 1 1/2" x 1 1/2" x 3/16" x 20"	2	lengths	820.00	1,640.00
	AIRCON PIPING SYSTEM				
	3/4" dia. Refrigerant pipe, soft drawn	24	ft.	110.00	2,640.00
	1/2" dia. Refrigerant pipe, soft drawn	24	ft.	65.00	1,560.00
	1/2 x 3/8" x 6' rubber insulation Superion	4	lengths	90.00	360.00
	3/4" x 3/4" x 6' rubber insulation Superion	4	lengths	210.00	840.00
	Polyethylene Tape	0.2	roll	860.00	172.00
	Adhesives	1	btl.	64.00	64.00
	Copper elbows, 3/4"	4	pcs.	50.00	200.00
	Copper elbows, 1/2"	4	pcs.	45.00	180.00
	Nitrogen	0.2	tnk	1,200.00	240.00
	Mapp gas	1	set	890.00	890.00
	Refrigerant	0.3	tnk	6,896.00	1,724.00
	Labor Cost			5,000.00	5,000.00