

**PROPOSAL REQUEST**  
Province of Bohol





PR No. \_\_\_\_\_ Date : **July 13, 2020**  
SAI No. \_\_\_\_\_ Date : \_\_\_\_\_  
ALOBS NO. \_\_\_\_\_ Date : \_\_\_\_\_

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
A.1.1(8)	4.00	Month	Provision of Field Office for the Engineer (Rental Basis)	P 8,505.00	P 34,020.00
B.4(1)	1.01	Km.	Construction survey and staking	P 39,532.98	P 39,928.31
B.5	2.00	each	Project Billboard / Signboard (8' x 8')	P 7,000.76	P 14,001.52
B.7	1.00	L.S.	Occupational Safety and Health Program	P 20,955.55	P 20,955.55
B.8(1)	4.00	Month	Traffic Management	P 7,027.43	P 28,109.73
B.9	1.00	L.S.	Mobilization /Demobilization	P 39,213.30	P 39,213.30
100(1)	0.61	ha.	Clearing & Grubbing (with Stripping)	P 205,319.77	P 125,245.06
101(4)a1	49.00	l.m.	Removal of Actual Structures/Obstruction, (610mmØ RCPC)	P 474.84	P 23,266.94
102(2)	738.00	cu.m.	Surplus Common Excavation (roadway & side ditch)	P 183.09	P 135,117.49
103(1)a	151.00	cu.m.	Structure Excavation (Common Soil)	P 292.88	P 44,224.97
103(6)a	319.00	cu.m.	Pipe Culverts and Drain Excavation (Common Soil)	P 292.88	P 93,428.90
104(1)a	243.00	cu.m.	Embankment from Roadway Excavation (Common Material)	P 292.06	P 70,970.24
105(1)a	5,213.00	sq.m.	Subgrade Preparation (Common Material)	P 20.27	P 105,687.64
200(1)	2,369.00	cu.m.	Aggregate Subbase Course (t=0.20m.)	P 1,175.36	P 2,784,418.30
311(1)c1	6,161.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	P 1,634.82	P 10,072,129.29
500(1)a3	63.00	ln.m.	Pipe Culverts 910 mm dia., Class II RCPC	P 5,629.07	P 354,631.72
505(2)a	264.00	cu.m.	Grouted Riprap, Class A (Slope Protection)	P 3,789.93	P 1,000,541.27
506(1)	116.00	cu.m.	Stone Masonry (Headwalls, Aprons, Catch Basins & Wingwalls)	P 4,591.10	P 532,567.48
605(1)a1	8.00	each	Warning Signs, (60cm triangle)	P 12,315.64	P 98,525.11
605(1)b1	6.00	each	Warning Signs, (75cm triangle)	P 12,555.04	P 75,330.23
605(6)e2	9.00	each	Hazard Markers (Chevron Signs), 600mm x 800mm	P 17,130.98	P 154,178.79
607(1)a	337.00	each	Solar Pavement Levelled Marker/Stud (Flush Type), Type G105	P 9,399.24	P 3,167,543.30
612(1)	265.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - White	P 952.37	P 252,376.97
612(2)	40.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - Yellow	P 976.26	P 39,050.22
624(1)a	10.00	set	Single Arm Post (8m), with Street Light, LED, 50W	P 69,453.77	P 694,537.69
					P 20,000,000.00

**Purpose/Remarks :** Furnishing of Labor, Materials and Equipment for the Concreting of Pob. (Talibon) - San Francisco Road, Talibon (CMGP)

Mode of Procurement : **Bidding**  
No. of days delivered : **116**  
Place of Delivery : **Project Site**  
To be awarded : **By lot**

**BY AUTHORITY OF THE GOVERNOR**

Requested By:	Cash Availability :	Approved by:
Signature  Printed Name <b>CAMILO L. GASATAN</b> Designation Provincial Engineer	Signature  Printed Name <b>EUSTAQUIO A. SOCORIN</b> Designation Provincial Treasurer	Signature  Printed Name <b>ATTY. KAT YENCE D. PIQUINTO</b> Designation PROVINCIAL ADMINISTRATOR Signature  Printed Name <b>ATTY. ARTHUR C. YAP</b> Designation Governor

PROVINCIAL RECEIVED BY: *[Signature]* DATE: *9/10/20*  
PROVINCIAL PROCUREMENT MANAGEMENT  
AMOUNT: *20,000,000.00*  
AS TO APP: \_\_\_\_\_

**PROVINCIAL BUDGET OFFICE**  
PROVINCE OF BOHOL  
CONTROL NO. *1098* REC'D BY: \_\_\_\_\_ DATE: *8/10/20*  
BENCHMARK NO. *1098* VALID UNTIL: *12/31/20*  
EXPENSE CODE *416-TP* AMOUNT *20,000,000.00*  
SOURCE: *CMGP* CONTROLLER: \_\_\_\_\_ DATE: *8/10/20*  
**PETER GOES M. RETUAL CPA**  
FBMO