


PR No. _____ Date : July 13, 2020
 SAI No. _____ Date : _____
 ALOBS NO. _____ Date : _____


Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
	5.00	Month	Provison of Field Office for the Engineer (Rental Basis)	P 8,505.00	P 42,525.00
B.4(1)	1.63	Km.	Construction survey and staking	P 39,532.98	P 64,438.76
B.5	1.00	each	Project Billboard / Signboard (8' x 8')	P 7,603.04	P 7,603.04
B.7(2)	1.00	L.S	Occupational Safety and Health Program	P 40,348.75	P 40,348.75
B.8(1)	5.00	Month	Traffic Management	P 6,374.53	P 31,872.63
B.9	1.00	L.S.	Mobilization /Demobilization	P 209,185.06	P 209,185.06
100(1)	1.47	ha	Clearing & Grubbing (with Stripping)	P 205,319.77	P 301,204.11
101(4)a1	28.00	cu.m.	Removal of Actual Structures/Obstruction, (610mmØ RCPC)	P 571.67	P 16,006.66
102(2)	2,121.75	cu.m.	Roadway Excavation (Surplus Common)	P 190.35	P 403,871.63
103(1)a	130.00	cu.m.	Structure Excavation (Common Soil)	P 292.88	P 38,074.47
103(6)a	1,930.00	cu.m.	Pipe Culverts and Drain Excavation (common soil)	P 292.88	P 565,259.51
104(1)a	905.00	cu.m.	Embankment from Roadway Excavation (Common Soil)	P 292.06	P 264,313.02
105(1)a	4,363.00	sq.m.	Subgrade Preparation (Common Material)	P 20.27	P 88,454.86
200 (1)	3,737.53	cu.m.	Aggregate Subbase Course (t=0.20m.)	P 1,082.49	P 4,045,837.21
311(1)c1	9,943.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	P 1,735.58	P 17,256,900.47
404(1)a	30,225.31	kg	Reinforcing Steel , Grade 40 , ASTM A-615	P 70.35	P 2,126,273.47
405(1)a3	336.96	cu.m.	Structural Concrete, 20.68MPa Class A, 28 days	P 9,243.77	P 3,114,781.94
500 (1) a3	45.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC	P 6,197.60	P 278,891.85
505(2)a	275.00	cu.m.	Grouted Riprap, Class A (Slope Protection)	P 3,851.18	P 1,059,075.24
506(1)	200.86	cu.m.	Stone Masonry (Lined Canal, headwalls, aprons, & wingwalls)	P 4,655.84	P 935,172.89
605(1)a1	6.00	each	Warning Signs, (60cm triangle)	P 14,265.54	P 85,593.23
605(1)b2	2.00	each	Warning Signs, (75cm triangle)	P 14,744.34	P 29,488.68
605(6)e2	8.00	each	Hazard Markers (Chevron Signs), 610mm x 914mm	P 19,011.56	P 152,092.45
607 (1) a	407.00	each	Solar Pavement Levelled Marker/Stud (Flush Type), Type G105	P 9,395.25	P 3,823,864.90
612(1)	395.45	sq.m.	Reflectorized Thermoplastic Pavement Markings (white)	P 952.37	P 376,614.84
612(2)	52.02	sq.m.	Reflectorized Thermoplastic Pavement Markings (yellow)	P 976.25	P 50,788.81
624(1)a1	13.00	each	Single Arm Post (8m), with Street Light, LED, 50W	P 69,167.50	P 899,177.52
					P 36,307,711.00


Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the Concreting of Pilar - Bagacay Road (CMGP Program)


Mode of Procurement : Bidding
No. of days delivered : 141 CD
Place of Delivery : Project Site
To be awarded : By lot

Requested By: 
Cash Availability : _____

Signature _____ **ATTY. KATHY D. PICQUINTO**
Printed Name CAMILO L. GASATAN **EUSTAQUIO A. SOCORIN**
Designation Provincial Engineer Provincial Treasurer **ARTHUR C. YAP**
 Governor

BY AUTHORITY OF THE GOVERNOR
 Approved by: 

2020-0676 RECEIVED BY:  DATE: 9/10/11
 PROVINCIAL PROCUREMENT MANAGEMENT UNIT
 PE # 0212 DC # _____ SC # _____ REG # _____
 AMOUNT: ₱ 36,307,711.00 AS TO APP: _____

PROVINCIAL BUDGET OFFICE
 PROVINCE OF BOHOL
 CONTROL NO. 1100 REC'D BY:  DATE: 9/10/11
 BARMARK NO. 1100 VALID UNTIL 12/31/11
 EXPENSE CODE 416-TF AMOUNT 36,307,711.00
 FUND SOURCE TF-CMGP
 PETER CESSM. RETUAL CPA
 FBMO