

The parties hereto, the Government of the Philippines, through the Department of Public Works and Highways, and the Contractor, have entered into this Contract, particularly but not limited to the implementation of the project as well as all applicable laws and regulations are deemed incorporated to and forming integral parts of this Contract.

5. In consideration of the payments to be made by the Owner to the Contractor, as earlier mentioned, the Contractor hereby covenants with the Owner to implement and complete the Project in conformity with the provisions of the Contract, the documents incorporated herein and the laws and regulations made integral parts hereof.
6. The Owner hereby covenants to pay advance payment to the Contractor of 15% of the total contract price upon approval of the Contract, issuance of Notice to Commence Work and the posting of irrevocable standby letter of credit of equivalent value. The Contractor hereby covenants to repay advance payment to the Owner by deducting 15% from his progress payment.

<b>CONCRETING OF POBLACION (SAGBAYAN)-SAGBAYAN SUR-KABASAKAN ROAD, SAGBAYAN, BOHOL</b>					
Item No.	QTY.	UNIT	Description of Supplies/Materials/Services	Unit Price	Amount
				(Pesos)	(Pesos)
A.1.1(3)	1.00	LS	CONSTRUCTION OF FIELD OFFICE FOR THE ENGINEER	69,438.60	69,438.60
B.4(1)	0.64	KM.	CONSTRUCTION SURVEY AND STAKING	28,229.50	28,229.50
B.5	1.00	EACH	PROJECT BILLBOARD/SIGNBOARD(8'x8')	7,761.60	7,761.60
B.7(2)	1.00	LS	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	81,716.04	81,716.04
B.9	1.00	LS	MOBILIZATION/ DEMOBILIZATION	130,200.00	130,200.00
100(1)	0.26	Ha.	CLEARING & GRUBBING	189,460.38	49,259.70
102(2)	812.71	CU.M.	Surplus Common Excavation (roadway & side ditch)	186.04	151,196.57
104(2)a	146.52	CU.M.	Embankment from borrow (Common Material)	1,066.10	156,204.97
105(1)a	2,001.00	SQ.M	Subgrade Preparation (Common Material)	19.75	39,519.75
200(1)	1,537.51	CU.M	Aggregate Subbase Course, 0.20m, Thk (includes shouldering)	1,047.58	1,610,664.73
311(1) c1	3,923.72	SQ.M	Portland Cement Concrete Pavement (Unreinforced)-0.23m thk, 14 days	1,618.15	6,349,167.52
506(1)	10.40	CU.M	Stone Masonry (line canal)	5,275.79	54,868.22
605(1) a1	4.0	EACH	Warning Signs, (600mm triangle)	21,966.45	87,865.80
605(1) b1	2.0	EACH	Warning Signs, (750mm triangle)	22,326.73	44,653.46
605(6) e2	3.0	EACH	Hazard Markers (Chevron Signs), 600 x 800mm	28,551.58	85,654.74
612(1)	157.73	SQ.M	Reflectorized Thermoplastic Pavement Markings-White	1,004.14	158,383.00
612(2)	6.81	SQ.M	Reflectorized Thermoplastic Pavement Markings-Yellow	1,059.72	7,216.69
624(1) a1	6.0	SET	Single Arm Post (8m), Solar LED Street Light, 50 Watts	65,126.36	390,758.16
			<b>Total</b>	<b>&gt;&gt;&gt;&gt;&gt;&gt;</b>	<b>₱9,492,596.43</b>
<b>Nine Million Four Hundred Ninety Two Thousand Five Hundred Ninety Six Pesos and Forty Three Centavos Only</b>					