

| Item No. | Quantity | Unit | Description | Estimated Amount |
|--|----------|-------------|--|------------------|
| PART A CONSTRUCTION OF LOUNGE, PRINTING ROOM & COMFORT ROOMS | | | | |
| 1001 | 86.67 | bd.ft. | Batterboard | 6,081.37 |
| 1002 | 28.88 | cu.m. | Excavation | 29,124.90 |
| Reinforced Concrete Works | | | | |
| 1003 | 1.46 | cu.m. | Reinforced Concrete Footing | 10,840.34 |
| 1003 (a) | 94.74 | kg. | Reinforcing Steel for Footings | 12,696.30 |
| 1003 (b) | 1.44 | cu.m. | Reinforced Concrete Column | 10,432.80 |
| 1003 (c) | 316.08 | kg. | Reinforcing Steel for Columns | 25,425.19 |
| 1003 (d) | 0.51 | cu.m. | Reinforced Concrete Stiffener Column | 3,749.29 |
| 1003 (e) | 86.21 | kg. | Reinforcing Steel for Stiffener Column | 37,583.54 |
| 1003 (f) | 1.14 | cu.m. | Reinforced Concrete Roof Beam | 9,047.20 |
| 1003 (g) | 258.20 | kg. | Reinforcing Steel for Roof Beam | 25,474.10 |
| 1003 (h) | 1.99 | cu.m. | Reinforced Concrete Wall Footing | 14,182.09 |
| 1003 (i) | 102.55 | kg. | Reinforcing Steel for Wall Footing | 25,066.57 |
| 1003 (j) | 3.01 | cu.m. | Reinforced Concrete Slab on Grade | 21,273.14 |
| 1003 (k) | 70.22 | kg. | Reinforcing Steel for Slab on Grade | 12,565.89 |
| Forms & Scaffoldings | | | | |
| 1003 (l) | 609.33 | bd.ft. | For Columns | 51,999.38 |
| 1003 (m) | 1,134.67 | bd.ft. | For Roof Beam | 85,920.06 |
| Masonry Works | | | | |
| 1003 (n) | 65.53 | sq.m. | Cement Plaster Finish | 53,642.70 |
| 1003 (o) | 133.54 | sq.m. | Roof Framing and Trusses | 32,847.02 |
| 1003 (p) | 623.75 | kg. | Pre-Painted Oven-Baked Metal Sheets | 74,537.58 |
| 1003 (q) | 54.00 | ln.m. | Interior & Roof Eave Ceiling using Cement Board on Light Metal | 59,492.00 |
| 1003 (r) | 48.20 | sq.m. | 4.5mm thick x 1.20m x 2.40m Hardiflex Cement Board on light gauge metal frame spaced at 0.60m on center bothways using 0.80mm x 12mm x 38mm carrying channel, 0.40mm x 19mm x 50mm double furring on ceiling board joists, 0.40mm x 19mm x 25mm single furring hangers and 0.40mm x 25mm x 25mm wall angle | 37,830.98 |
| Doors and Windows | | | | |
| 1010 | 12.56 | sq.m. units | Wooden and PVC Doors and Window Jamb | 21,867.32 |
| 1010 | 7.00 | units | Doors and Window Glass | 78,175.58 |
| 1 unit - Open Back Analok Aluminum Frame, Three Panes using 1/4" thick Clear Glass, Sliding Window, 1.80m x 1.20m 1 unit - Open Back Analok Aluminum Frame, Two Panes using 1/4" thick Clear Glass, Sliding Window, 1.20m x 1.20m 1 unit - Open Back Analok Aluminum Frame, Single Pane using 1/4" thick Clear Glass, Fix Window, 0.60m x 1.20m 2 units - Open Back Rectangular Tube Analok Aluminum Frame, Two Panes using 1/4" thick Clear Glass, Sliding Door/Fix Window, 1.60m x 2.10m 2 units - A1 Jalousie Aluminum Frame, 6 Blades using 1/4" x 20" Clear Glass, Jalousie Blades, 0.60m x 0.60m | | | | |
| 1018 | 58.28 | sq.m. | Tileworks | 86,331.42 |
| Plumbing Works | | | | |
| 1002 (4) | 123.00 | pc. | Sanitary Pipes and Fittings | 20,753.69 |
| 1002 (5) | 20.00 | set | Plumbing Fixtures and Accessories | 49,304.77 |
| Electrical Works | | | | |
| 1100 | 1.00 | lot | Conduits, Boxes and Fittings | 8,387.64 |
| 1101 | 1.00 | lot | Wires and Wiring Devices | 41,115.65 |
| 1102 | 1.00 | set | Panel Board | 6,520.50 |
| 1103 | 1.00 | lot | Lighting Fixtures | 3,113.94 |
| 1032 | 139.69 | sq.m. | Painting Works | 35,808.17 |
| PART B CONSTRUCTION OF PERIMETER FENCE | | | | |
| 1003 | 163.33 | bd.ft. | Batterboard | 11,294.56 |
| 803 | 0.66 | cu.m. | Structure Excavation | 950.91 |
| 900 | 0.79 | cu.m. | Reinforced Concrete Works | 6,683.51 |
| 902 | 42.64 | kg. | Reinforcing Steel Works | 12,305.95 |
| 1053 | 1.00 | m. | Metal Works | 76,017.11 |
| 1032 (a-1) | 146.83 | sq.m. | Steel Painting Works | 11,177.78 |
| 903 | 66.67 | bd.ft. | Column Pedestal Form | 3,127.67 |

TOTAL ESTIMATED CONTRACT COST: P 1,112,748.59

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the
CONSTRUCTION OF SUPPORT FACILITIES FOR CONTAINERIZED PCR LABORATORY
at BOHOL MEDICAL CARE INSTITUTE, J.A. CLARIN STREET, DAO DISTRICT, TAGBILARAN CITY

Mode of Procurement : **Bidding**
 No. of days delivered : **60 Calendar Days**
 Place of Delivery : **Project Site**
 To be awarded : **By lot**

Requested By: _____ Cash Availability : _____

Signature:  **CESAR TOMAS M. LOPEZ, MD**
 Designation: Provincial Health Officer I

Signature:  **EUSTAQUIO A. SOCORIN**
 Designation: Provincial Treasurer

BY AUTHORITY OF THE GOVERNOR
 Signature:  **HON. ARTHUR C. YAP**
 Designation: Governor