

1013	Replacement of Pre- Painted Metal Roofing Sheets	Sq.m	159.5	935.00	149,132.50
1003 (1)B2	Ceiling Works				
A.	New Gypsum Ceiling Board on Wooded Ceiling Joists for Interior Ceiling including Replacement of Dilapidated Joists	Sq.m	88.0	649.10	57,120.80
B.	Spandrel Exterior/ Eave Ceiling and Total Replacement of Wooden Ceiling Joists	Sq.m	47.7	1,404.680	66,860.14
1009	New Glass Jalousie Windows Including Replacement of Dilapidated Jambs and Installation of Window Grills	Sq.m	21.25	5,257.60	111,724.00
1010	Wooden Doors	Sq.m	12.56	4,215.382	52,945.20
1043	PVC Toilet Doors	Sq.m	2.94	3,064.286	9,009.00
1018	Tileworks				
A.	Floor Tiles	Sq.m	76.88	1,515.504	116,511.95
B.	Tiles for Two Units Toilet and Bath	Sq.m	21.08	2,600.095	54,810.00
C.	Tiles for Façade Plant Box	Sq.m	2.47	3,287.0054	8,118.90
	Total Revamp of Electrical Works				
1100	Conduit, Boxes and Fittings	Lot	1.0	29,490.30	29,490.30
1101	Wires and Wiring Devices	Lot	1.0	109,248.30	109,248.30
1102	Panel Board	Set	1.0	13,255.20	13,255.20
1103	Lightning Fixtures and Aircon Units	Set	1.0	180,608.40	180,608.40
1002	Plumbing (Total Replacement of Plumbing Fixtures, Revamp of Water Lines and Santary Lines	Lot	1.0	83,745.40	83,745.40
1032 (1)a	Painting of Concrete and Masonry Structures	Sq.m	232.97	200.056	46,607.046
1032 (1)b	Painting of Interior Ceiling	Sq.m	88.0	482.187	42,432.456