

## PURCHASE REQUEST

Province of Bohol

Department : <b>Provincial Engineer's Office</b>	PR No. _____	Date : <b>May 20, 2021</b>
Section : _____	SAI No. _____	Date : _____
_____	ALOBS NO. _____	Date : _____

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
A.1.1(3)	1.00	LS	Construction of Field Office for the Engineer	P 21,276.28	P 21,276.28
B.4(1)	1.00	km.	Construction Survey and Staking	P 39,532.98	P 39,532.19
B.5	1.00	each	Project Billboard / Signboard (8' x 8')	P 7,538.13	P 7,538.13
B.7	1.00	L.S.	Occupational Safety and Health Program	P 26,913.96	P 26,913.96
B.9	1.00	L.S.	Mobilization /Demobilization	P 89,301.45	P 89,301.45
100(1)	0.40	ha.	Clearing & Grubbing	P 205,619.40	P 82,247.76
101(4)a1	8.00	l.m.	Removal of Actual Structures/Obstruction, (610mmØ RCPC)	P 477.58	P 3,820.66
101(4)a4	6.00	l.m.	Removal of Actual Structures/Obstruction, (1070mmØ RCPC)	P 716.37	P 4,298.24
102(2)	398.00	cu.m.	Surplus Common Excavation (roadway & side ditch)	P 183.27	P 72,942.77
103(1)a	228.00	cu.m.	Structure Excavation (Common Soil)	P 293.92	P 67,014.88
103(6)a	108.00	cu.m.	Pipe Culverts and Drain Excavation (Common Soil)	P 293.92	P 31,156.04
104(2)a	746.00	cu.m.	Embankment from Borrow (Common Material)	P 1,098.44	P 819,438.33
105(1)a	1,641.00	sq.m.	Subgrade Preparation (Common Material)	P 20.32	P 33,351.36
200(1)	2,324.00	cu.m.	Aggregate Subbase Course, 0.20m.thk. (includes shouldering)	P 1,402.86	P 3,260,243.85
311(1)c1	6,100.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	P 1,738.08	P 10,602,296.45
500(1)a3	9.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC	P 5,887.53	P 52,987.74
500(1)a4	11.00	ln.m.	Pipe Culverts 1070 mm dia. , Class II RCPC	P 6,471.59	P 71,187.51
502(4)	75.00	each	Lined Ditch Concrete Cover (0.90m. X 0.50m. X 0.15m.)	P 1,268.58	P 95,143.28
505(2)a	512.00	cu.m.	Grouted Riprap, Class A (Slope Protection)	P 3,900.77	P 1,997,194.03
506(1)	182.00	cu.m.	Stone Masonry (Headwalls, Aprons, Wingwalls, Parapet & Lined Canal)	P 4,708.96	P 857,031.10
605(1)a1	2.00	each	Warning Signs, (600mm triangle)	P 12,404.90	P 24,809.80
605(6)e2	3.00	each	Hazard Markers (Chevron Signs), 600 x 800mm	P 17,224.32	P 51,672.96
612(1)	248.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - White	P 954.18	P 236,635.93
612(2)	5.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - Yellow	P 978.07	P 4,890.33
624(1)a1	20.00	set	Single Arm Post (6m.), Solar LED Street Light, 50 watts	P 68,976.20	P 1,379,523.91
SPL	4.00	each	PEO RROW Marker	P 2,528.69	P 10,114.77
<b>TOTAL</b>				<b>P</b>	<b>19,942,563.72</b>

**Purpose/Remarks :** *Inter-* Furnishing of Labor, Materials and Equipment for the Concreting of Pob. (Guindulman) - Casbu - Bato Road

Road I.D. No. : 07BOH104-20%DF-2021-0177 *PR# 0028*

Mode of Procurement : **Bidding**

No. of days delivered : **160**




Place of Delivery : **Project Site**

To be awarded : **By lot**

**RECEIVED BY: [Signature] DATE: 6/2/21**

**PROVINCIAL PROCUREMENT MANAGEMENT UNIT**

**AMOUNT: ₱19,942,563.72**

Requested By:	Cash Availability:	Approved by:
Signature  Printed Name <b>CAMILO L. GABATAN</b> Designation Provincial Engineer	 <b>EUSTAQUIO A. SOCORIN</b> Provincial Treasurer	 <b>ATTY. ARTHUR C. YAP</b> Governor

**PROVINCIAL BUDGET OFFICE**  
**PROVINCE OF BOHOL**

CONTROL NO. **694** REC'D BY: *[Signature]* DATE: **5/27/21**

FORM NO. **1785** VALID UNTIL: **12/31/2021**

EXPENSE CODE: **891801/50703010-227** P1 9,942,563.72

FUND SOURCE: **2020-6400** AMOUNT: **867** DATE: **5/27/2021**

**PETER P. M. R. TALICPA**  
**BMO**

**CHARGED TO:**  
**2020 WFOI-2021**

SIG: *[Signature]* DATE: **5/27/21**

**INTERNAL CONTROL DIVISION**

①