

			SCOPE OF WORK	UNIT COST	AMOUNT
2.			<b>At Main Hospital Building</b>		
			<b>Air Conditioning Unit for O.B Gyne Reception &amp; Waiting Area, Minor O.R, Resuscitation Room, Semi Private Ward, O.B. Gyne Wards &amp; C.S./O.R. Delivery Room (1 unit each)</b>		
	6.00	set	1.) Supply and Installation of Air Conditioning unit Split Type Wall Mounted Full DC Inverter 1.5 HP Installed at O.B. Gyne Reception, Minor O.R. Resuscitation Room, Semi Private Ward, O.B. Wards and C.S. O.R. Delivery Room, 1 unit each	P 66,592.89 P	399,557.31
			<b>Air Conditioning Unit for Labor Room</b>		
	1.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz	P 75,469.41 P	75,469.41
			<b>Air Conditioning Unit for O.B. Gyne Nurses Station &amp; High Risk Pregnancy Room</b>		
	2.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz	P 57,074.22 P	114,148.44
			<b>Air Conditioning Unit for O.R. Nurses Station / Nursery</b>		
	1.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 67,119.54 P	67,119.54
			<b>Air Conditioning Unit for NICU Breast feeding &amp; New Born Care</b>		
	1.00	set	1.) 1.0HP Split Type Wall Mounted Full DC Inverter Air Conditioning Unit installed at NICU/Breastfeeding & New Born Care	P 57,617.06 P	57,617.06
			<b>Air Conditioning Unit for Major O.R. &amp; Operating Room (near sterile corridor)</b>		
	1.00	unit	1.) Air Conditioning Unit System Mini IXV Inverter Type System-(2) Two Type Ceiling Cassette Indoor Units connected to one Outdoor Unit, 6.0HP Capacity, Full Converter Refrigerant installed at Major O.R.	P 210,400.00 P	210,400.00
	2.00	units	2.) Mini IXV Indoor Unit 4-Way Ceiling Cassette 3.0 HP Capacity installed at Operating Room and Sterile Corridor with Piping Refrigerant Kit	P 74,115.69 P	148,231.38
3.			<b>For Emergency Department &amp; Pediatric Ward</b>		
			<b>Air Conditioning Unit for Emergency Department/Nurses Station, Examination Area, Observation Area</b>		
	1.00	set	1.) A/C Unit 4.0HP, Nominal Cooling Capacity, 4 Way Ceiling Cassette Full DC Inverter Technology equipped with Over Voltage protection relay that protects the unit from damage caused by over voltage, Japan made high efficiency scroll compressor, wired remote controller.	P 255,970.34 P	255,970.34
	1.00	set	2.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.5HP, equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 84,419.46 P	84,419.46
	1.00	set	3.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 70,567.25 P	70,567.25
			<b>Air Conditioning Unit for Female Pedia Ward</b>		
	1.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 3.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 97,458.40 P	97,458.40
			<b>Air Conditioning Unit for Male Pedia Ward &amp; Semi Private Ward 2</b>		
	2.00	sets	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 77,487.55	P 154,975.09
			<b>Air Conditioning Unit for Semi Private Ward 1</b>		
	1.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.5HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 65,759.73 P	65,759.73
			<b>Air Conditioning Unit for Isolation Room &amp; Semi-Private Ward 3</b>		
	2.00	sets	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 58,469.11 P	116,938.21
			<b>Air Conditioning Unit for Doctors &amp; Nurses Station</b>		
	1.00	set	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 0.8HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 54,821.90 P	54,821.90