



			UNIT COST	AMOU
5.	1.00	set	<b>Air Conditioning Unit for Radiologist Office/Reception &amp; Waiting Area</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, Three DC Inverter Components, Inverter Compressor, Inverter Module and Inverter Fan Motor. Purifies indoor air by eliminating molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, 3d movement swing blades, 3.5 cooling capacity, wireless remote, 230 volts, 1ph, 60 hz	P 145,885.96 P 14
	1.00	set	<b>Air Conditioning Unit for CT Scan Room</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 76,516.26 P 76,516.26
	1.00	set	<b>Air Conditioning Unit for Mammo Room</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.5HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 69,285.52 P 69,285.52
	2.00	sets	<b>Air Conditioning Unit for Digital X-Ray Room &amp; Control Room</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	P 56,063.00 P 112,125.99
	1.00	set	<b>For Medical Wards</b> <b>Air Conditioning Unit for Patients Waiting Area</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 3.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 97,458.39 P 97,458.39
	2.00	sets	<b>Air Conditioning Unit for Female Medical Wards Service Hallway at Doctor's Clinic</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 76,956.58 P 153,913.15
	4.00	sets	<b>Air Conditioning Unit for Female Medical Wards/Semi-Private Wards 1 &amp; 2 &amp; Semi Private near Nurses Station</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.5HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 66,420.21 P 265,680.84
	2.00	sets	<b>Air Conditioning Unit for Polmunary Clinic &amp; Dental Clinic</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 57,212.36 P 114,424.72
	1.00	set	<b>Air Conditioning Unit for Doctor's Clinic &amp; Nurses Station</b> 1.) A/C Unit 4.0HP, Nominal Cooling Capacity of 11.2 kw., Ceiling Cassette Full DC Inverter Technology (Inverter Compressor, Inverter Module and Inverter Fan Motor) equipped with Over Voltage protection relay that protects the unit from damage caused by over voltage, Japan made high efficiency scroll compressor, wired remote controller.	P 258,126.89 P 258,126.89
	6.	1.00	set	<b>For Surgical Wards</b> <b>Air Conditioning Unit for 2 General Rooms near O.R.</b> 1.) Mini IXV A/C System Outdoor Unit, 5.0 HP Capacity, Full DC Inverter, Refrigerant used; R410A, Model RAM-160FPSQB, 230V, 1Ph, 60Hz
2.00		sets	2.) Mini IXV Indoor Unit 4-Way Ceiling Cassette 2.5 HP Capacity, Model RCI - 2.5 FSN1Q, 230V, 1Ph, 60Hz, Wired Remote Controller, Model PC-AR, Refrigerant Piping kit, Model E-NP2825	P 73,831.98 P 147,663.96
1.00		set	<b>Air Conditioning Unit for Receiving &amp; Releasing/Blood Extraction.</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.5HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 88,872.18 P 88,872.18
2.00		sets	<b>Air Conditioning Unit for Female Surgical Ward &amp; Clinical Laboratory</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 2.5HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 77,595.47 P 155,190.94
4.00		sets	<b>Air Conditioning Unit for Microbiology, Semi Private Surgical Ward &amp;</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 60,355.03 P 241,420.12
3.00		sets	<b>Air Conditioning Unit for Private Ward, Male Surgical and Pre-Op &amp;</b> 1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, Wireless remote, 230 volts, 1ph, 60 hz,	P 53,434.75 P 160,304.25