

B-II	Concrete Works: 78 column	Cu.m	18.0	66,939.77	1,204,515.86
B-IIA	Supply and Installation of Exterior Stone Finish	Sq.m	75.0	2,695.57	202,167.75
B-IIB	Masonry: Lower CHB4 Wall	Sq.m	166.5	1,357.67	226,052.06
B-IIC	CHB Zocalo	Cu.m	16.65	7,638.04	127,173.37
B-IID	Two Faces Plastering	Sq.m	105.0	403.00	42,315.00
B-III	Demolition Works (74 Col. Unit)	Sq.m	491.0	121.98	59,892.18
B-IIIA	Removal of the Perimeter Fence with Steel Grill	Lot	1.0	90,182.40	90,182.40
B-IIIB	Removal of Side Walk Concrete (Fence 1,2 and 4)	Cu.m	17.0	1,951.28	33,171.76
B-IIIC	Concrete Works of Existing Sidewalk	Cu.m	17.0	8,831.69	150,138.73
B-IV	Equipment	Lot	1.0	139,738.80	139,738.80
B-V	Forms and Scaffolding	Lot	1.0	319,832.76	319,832.76
B-VI	Painting Works	Lot	1.0	267716.80	267716.80
C.	IMPROVEMENT OF CPG PARK LIGHTNINGS				
C-I	Earthworks				
C-Ia.1	Post Lamps Pedestal Excavation Footing (99 units):(0.75m x 0.75m x 0.7m)	Cu.m	38.98125	1,220.04	47,558.68
C-Ia.2	Post Lamps (Underground Electrical Wire Connection)	Cu.m	62.10	1,220.03	75,763.86
C-Ia.3	Removal of Deadwood (Bagawnga Tree)	Lot	1.0	3,660.95	3,660.95
C-Ib.1	Pedestal Excavation Footing (30units): (0.75m x 0.75m x 1.0m)	Cu.m	16.875	1,219.99	20,587.33
C-Ib.2	Pedestal with Circuit Breaker Excavation (Underground Electrical Wire Connection)	Cu.m	28.845	1,219.94	35,189.17
C-II	CONCRETE WORKS				
C-II a.1	Post Lamps Reinforced Concrete Pedestal Column & Footing (99units)	Cu.m	17.325	21,139.62	366,243.92

101210636 *gm*