

			12,393.72	173,512.1	
	4.00 3.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00	unit unit unit unit unit unit unit unit unit unit	Supply of Materials and labor in the installation of Aluminum Framed Windows: Sliding window 4 pan FSSF 2.94 x 0.90 pcw/temp. 6mm clear Sliding window 3 pan SSS 2.26 x 0.90 pcw/temp. 6mm clear Sliding window 2 pan SS 1.50 x 1.40 w/tr pcw/temp. 6mm clear Sliding window 2 pan SS 1.40 x 0.80 pcw/temp. 6mm clear Fixed counter glass w/ 2 counter holes & notch 1.92 x .95 pc Fixed glass w/ 2.40 x 0.70 pcw/temp. Cl ¼ Sliding window 2 pan SS 1.5 x 0.60 pcw/temp. 6mm clear Sliding window 3 pan SSS 2.0 x 0.60 pcw/temp. 6mm clear Sliding window 2 pan SS 1.0 x 0.60 pcw/temp. 6mm clear	P	P
1005(6)	1.00	lot	WINDOW GRILLS	21,534.19	21,534.19
PART M	ELECTRICAL WORKS			P 21,534.19	P 21,534.19
1100	1.00	lot	CONDUIT, BOXES AND FITTINGS Supply of Materials, Labor and Equipment for Electrical Conduit, Boxes, and Fittings using the following: 1/2" dia.PVC Electrical Conduit Pipe, Orange, HD, 3m/pc 1/2"dia PVC Electrical Conduit Elbow 90 deg. 1/2"dia PVC Electrical Conduit Male Adaptor w/locknut 3/4"dia PVC Electrical Conduit Pipe, Orange, HD, 3m/pc 3/4"diaPVC Electrical Conduit Elbow 90 deg. 3/4"dia PVC Electrical Conduit Male Adaptor w/locknut 65mmØ PVC Conduit, HD 180m 65mmØ PVC Conduit, HD ELBOW Octagonal Box,with cover PVC,Orange 2 x 4 Utility box, Orange Pull Box, 300mm x 300mm x 100mm Steel 3"dia. Weather proof service head (Entrance Cap)	P	P
	412.00 72.00 365.00 12.00 2.00 8.00 60.00 2.00 113.00 100.00 4.00 1.00	pc. pc. pc. pc. pc. pc. pc. pc. pc. pc. pc. pc.		131,775.56	131,775.56
1101	1.00	lot	WIRES AND WIRING DEVICES Supply of Materials, Labor and Equipment for Electrical Wires and Wiring devices using the following: 2.0 sq.mm THHN CU.Wire, Stranded 3.5 sq.mm THHN CU.Wire, Stranded 5.5 sq.mm THHN CU.Wire, Stranded 8.0 sq.mm THHN CU.Wire, Stranded 38 sq.mm THHN CU.Wire, Stranded 22 sq.mm THHN CU.Wire, Stranded 200 sq.mm THHN CU.Wire, Stranded 100 sq.mm TW CU.Wire, Stranded, Grounding 22.0 sq.mm TW CU.Wire, Stranded, Grounding 8.0 sq.mm TW CU.Wire, Stranded, Grounding 14 sq.mm TW CU.Wire, Stranded, Grounding Three Spool Secondary track (porcelain wire holder) Ground Rod, 16mme x 8 ft. 0.16mm x 19mm x 16m PVC Electrical Insulating tape,Nitto Butyl Rubber Tape No. 15 Nitto	P	P
	140.00 1,510.00 959.00 58.00 30.00 30.00 120.00 45.00 15.00 15.00 29.00 2.00 2.00 66.00 12.00	m. m. m. m. m. m. m. m. m. m. m. m. pc. roll pc.		707,558.31	707,558.31
1102 (1)	4.00	set	PANEL BOARD WITH MAIN & BRANCH BREAKERS Supply of Materials, Labor and Equipment for Panel Board with Main & Branch Breakers using the following: Dist. Panelboard(DP1), 20 Branches,Bolt-on Type, 3Phase, complete with the following breakers: 1 pc - 3P, 120 Amp, Main CB 4 pc - 2P, 15 Amp, Branch CB 7 pc - 2P, 20 Amp, Branch CB 9 pc - 2P, 30 Amp, Branch CB Dist. Panelboard(DP2), 12 Branches, Bolt-on Type,3Phase complete with the following breakers: 1 pc - 3P, 125 Amp, Main CB 12 pc - 2P, 20 Amp, Branch CB Main Panelboard, 4 Branches, Bolt-on Type, 3Phase complete with the following breakers: 1 pc - 3P,500 Amp, Main CB 1 pc - 3P, 125 Amp, Branch CB 1 pc - 3P, 150 Amp, Branch CB 1 pc - 3P,100 Amp, Branch CB 1 pc - 3P,60 Amp, Branch CB Water Treatment Panelboard, 4 Branches, Bolt-on Type, 1Phase complete with the following breakers: 1 pc - 100 Amp. 1P, CB Main 4 pc - 30 Amp. 1P, CB branch brkr.	P	P
	1.00 1.00 1.00	set set set		92,274.00	369,096.02
1103	1.00	lot	LIGHTING FIXTURES AND EXHAUST FAN Supply of Materials, Labor and Equipment for Lighting Fixtures using the following: 20 Watts LED Downlight Lighting Fixture, Recessed Mtd. 2 x 40 Watts, LED Tube Lighting Fixture 1P, 1Gang Switch,Flush type 1P, 2Gang Switch,Flush type 230 volts Duplex Receptacle Outlet 230 volts Receptacle Outlet (1 Gang)ExFan1/Em.Light Exhaust Fan Wall mounted(toilet) Exhaust Fan Ceiling mounted(toilet) Emergency Light, 2 Head Lamp Tri-Top ACU Outlet, Flush type	P	P
	6.00 41.00 13.00 2.00 35.00 13.00 6.00 1.00 10.00 13.00	set set pc. pc. pc. pc. set set pc. set		176,674.27	176,674.27
1200(3)	4.00	unit	ROOM AIR-CONDITION UNITS FOR DIALYSIS CENTER Supply of Materials, Labor and Equipment for the Installation of Dialysis Center Room Air-Conditioning Units including Piping System Airconditioning Unit, Wall Mounted Split Type A/C, 3 in 1 Full DC Inverter Components - Inverter Compressor, Inverter Module, and Inverter Fan Motor; equipped with Nano Silver and Photocatalyst filter and Anti-Allergy Agent filter, easy to clean panel, auto restart function, auto protection mode, wireless remote, 2.0Hp Cooling Capacity, Model RAS-19HT/RAC-19HTP, 230v/1ph/60hz.	P	P
a.				89,020.31	356,081.22
b.	1.00	unit	FOR STAFF ROOM Supply of Materials, Labor and Equipment for the Installation of Staff Room Air-Conditioning Units including Piping System Window Type airconditioning unit, full DC inverter, compact size, 0.8Hp capacity, dual fan motors, self-diagnose function, AION filter, eco-friendly refrigerant, high efficiency ratio, user-friendly remote control, 230v, 1ph, 60hz	P	P
				37,287.36	37,287.36