

1018(B)	HAND WASHING COUNTER(INCLUDING LEG FINISH)	SQ.M.	4.42	3,120.00	13,790.40
1018(C)	COUNTER TOP IN TOILET(INCLUDE LEG FINISH)	SQ.M.	5.1	3,800.00	19,380.00
1047(8)	ROOF FRAMING AND TRUSSES	KG.	5,551.55	100.00	555,155.00
1047(10)	WATER TANK PLATFORM METAL WORKS	KG.	1,007.02	100.00	100,702.00
1051	STAIR, RAMP AND CORRIDOR RAILINGS	PC.	63.00	1,660.00	104,580.00
1032 (A-1)	STEEL PAINTING WORKS	LOT	1.00	63,100.00	63,100.00
1053	TEMPORARY STAIR (STEEL)				
A.	STAIR	UNIT	1.00	232,880.00	232,880.00
B.	REINFORCED CONCRETE WORKS FOR TEMPORARY STAIR	CU.M.	2.66	7,700.00	20,482.00
C.	REINFORCING STEEL FOR TEMPORARY STAIR	KG.	173.66	70.00	12,156.20
1003 (1)E1	INTERIOR CEILING USING METAL FRAME & FIBER CEMENT BOARD CEILING	SQ.M.	108.31	1,890.00	204,705.90
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR THE FIBER CEMENT BOARD CEILING 10MM THICK X 1.20M X 2.40M X GYPSUM BOARD ON LIGHT GAUGE METAL CEILING JOIST SPACED AT 0.60M ON CENTER BOTHWAYS USING 0.80MM X 12MM X 38MM CARRYING CHANNEL, 0.40MM X 19MM X 50MM DOUBLE FURRING ON CEILING BOARD JOISTS, 0.40MM X 19MM X 25MM SINGLE FURRING HANGERS AND 0.40MM X 25MM X 25MM WALL ANGLE, INTERIOR CEILING				
1003 (1)E2	EXTERIOR CEILING USING SPANDREL ON LIGHT METAL FRAMES	SQ.M.	34.76	2,800.00	97,328.00
	0.40MM X 0.110M X LS METAL CEILING, CEILING BOARD, SPANDREL(WHITE) USING 0.40MM X 0.19MM X 50MM DOUBLE FURRING CEILING JOIST AND POWDER COATED, WHITE				