

	SUPPLY & INSTALLATION OF 12MM SQUARE BAR WINDOW GRILLE FOR WINDOW 2 AT GROUND FLOOR				
1100	CONDUIT, BOXES AND FITTINGS	LOT	1.00	121,700.000	121,700.00
1101	WIRES & WIRING DEVICES	LOT	1.00	133,000.000	133,000.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR ELECTRICAL WIRES AND WIRING DEVICES USING THE FOLLOWING:				
	570M-3.5 SQ.MM THHN CU.WIRE				
	152M-5.5 SQ.MM THHN CU.WIRE				
	65M-14.0 SQ.MM TWN CU.WIRE, GROUNDING				
	130M-30.0 SQ.MM THWN CU. MAIN WIRE				
	CABLE:				
	60M-30 SQ.MM THHN. STRANDED, CU.CABLE				
	15M-22 SQ.MM THHN, STRANDED, CU. CABLE				
	15M-8.0 SQ.MM THHN, STRANDED CU. CABLE				
	30M-14 SQ.MM TW, STRANDED, CU.CABLE(GROUNDING)				
	7M-5.5 SQ.MM TW, STRANDED, CU.CABLE(GROUNDING)				
	7M-8.0 SQ.MM TW, STRANDED, CU. CABLE(GROUNDING)				
1102(1)	PANEL BOARD WITH MAIN & BRANCH BREAKERS	SET	3.00	33,000.000	99,000.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR PANEL BOARD WITH MAIN & BRANCH BREAKERS USING THE FOLLOWING:				
	1 SET- PANELBOARD (DPA), 12 BRANCHES 1PH, CU BUSBAR, 125 AT, 150AF MAIN COMPLETE WITH THE FOLLOWING BREAKERS:				
	1 SET- 125 AT, 1 POLE				
	6 SET-15 AT, 2 POLE				
	6 SET- 20 AT, 2 POLE				
	1 SET-PANELBOARD PPH, 4 BRANCHES, 1PH, CU BUSBAR, 50AT/50AF, MAIN COMPLETE WITH THE FOLLOWING BREAKERS.				