



# **PURCHASE ORDER** **GOVERNOR'S OFFICE**

Agency / Requisitioning Office

|                |  |                            |
|----------------|--|----------------------------|
| Supplier       | <b>SAMMY'S AIRCONDITIONING &amp; REFRIGERATION SERVICES &amp; REPAIR SHOP</b>  | D.O. No. P.O. NO. 2021-345 |
| Address :      | <b>0178, Courtyard Building, Airport Road, Cogon District, Tagbilaran City</b> | Date : August 11, 2021     |
| E-mail Address | <b>plumabang@yahoo.com</b>   | Mode of                    |
| Telephone No.  | <b>343-0328</b>  | Procurement :              |
| TIN            | <b>146-817-710-000</b>   | <b>PUBLIC BIDDING</b>      |

Gentlemen/Mesdames:

Please furnish this Office the following articles subject to the terms and conditions contained herein:

|                     |   |                 |                                    |
|---------------------|---|-----------------|------------------------------------|
| Place of Delivery : | <b>GOVERNOR'S OFFICE</b>                        | Delivery Term : | <b>Please read at the</b>          |
| Address :           | <b>New Capitol Site, Tagbilaran City, Bohol</b> |                 | <b>back hereof.</b>                |
| Date of Delivery :  | <b>within 30 days upon receipt of NTP</b>       | Payment Term :  | <b>upon completion of delivery</b> |
| Warranty Period:    | <b>1 year warranty</b>                          |                 |                                    |

| ITEM | UNIT    | DESCRIPTION  | QTY. | UNIT COST  | AMOUNT     |
|------|---------|--|------|------------|------------|
| 1    | SET     | FLOOR MOUNTED FULL DC-INVERTER PACKAGE A/C,5-Ohp, Cooling capacity of 50,420 kj/hr., floor mounted charge with ozone-friendly refrigerant(RA10A, equipped with the following safety devices so as to protect the unit from total damage compressor overcurrent relay, compressor discharge thermostat, high pressure switch, reverse phase protection relay, fuse for control circuit and fuse for outdoor unit fan motor; Model RPS-140AN/RAC-140-RPS, 230V/3ph/60hz.Compressor Warranty: 5 years, other parts: 1 year - HITACHI UTOPIA | 1    | 249,719.00 | 249,719.00 |
|      | pc.     | INSTALLATION MATERIALS, EQUIPMENTS SUPPORT, DRAINS, CIRCUIT BREAKERS, WIRES, TAPES AND ACCESSORIES   |      |            |            |
|      | pc.     | Service Circuit Breaker, 60A, 3Ph, 60hz, NEMA 3R Enclosure   | 1    | 2,780.00   | 2,780.00   |
|      | meters  | # 08 AWG THHN Philflex   | 6    | 70.00      | 420.00     |
|      | meters  | # 12 AWG THHN Philflex   | 70   | 40.00      | 2,800.00   |
|      | lengths | PVC Electrical Pipe, orange,3/4"   | 8    | 144.00     | 1,152.00   |
|      | pcs.    | PVC Elbow, Orange, 3/4"  | 6    | 40.00      | 240.00     |
|      | lengths | PVC Pipe, Blue 1"  | 6    | 160.00     | 960.00     |
|      | pcs.    | PVC Elbow, blue 1"   | 4    | 20.00      | 80.00      |
|      | sets    | Expansion Shield with lag screw  | 8    | 90.00      | 720.00     |
|      | pcs.    | Silver Rod   | 3    | 80.00      | 240.00     |
|      | pcs.    | Welding Rod  | 75   | 10.00      | 750.00     |
|      | pcs.    | Bolts, nuts and washers  | 4    | 15.00      | 60.00      |
|      | lengths | Angular Bar 1 1/2 x 1 1/2 x 3/16" x 20'  | 2    | 810.00     | 1,620.00   |
|      |         | AIRCON PIPING SYSTEM   |      |            |            |
|      | ft.     | 3/4 dia. Refrigerant Pipe, Soft drawn  | 75   | 115.00     | 8,625.00   |
|      | ft.     | 1/2 dia. Refrigerant pipe, soft drawn  | 75   | 67.00      | 5,025.00   |
|      | lengths | 1/2 " x 3/8" x 6 rubber insulation superlon  | 13   | 90.00      | 1,170.00   |
|      | lengths | 1/4 x 1" x 6' rubber insulation superlon   | 13   | 255.00     | 3,315.00   |