

**PURCHASE REQUEST**

Province of Bohol

Department : **Provincial Engineer's Office**

PR No. \_\_\_\_\_ Date: **March 11, 2021**

Section :

SAC No. \_\_\_\_\_ Date: \_\_\_\_\_

ALDPS NO. \_\_\_\_\_ Date: \_\_\_\_\_

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
<b>PART A GENERAL REQUIREMENTS</b>					
B.3	1.00	lot	PERMITS & CLEARANCES Application and Processing of Building Permit with the Office of the Building Official	6,300.00	6,300.00
B.7	1.00	lot	SAFETY AND HEALTH	2,185.60	2,185.60
B.5	1.00	unit	PROJECT BILLBOARD (4'x 8') (TARPAULIN W/ STANDARD	2,871.79	2,871.79
<b>PART B EARTHWORKS</b>					
803 (1)	31.30	cu.m.	STRUCTURE EXCAVATION	2,278.22	71,308.26
804 (1)b	106.60	cu.m.	EMBANKMENT (Selected Borrow)	857.07	91,363.36
804 (4)	9.50	cu.m.	GRAVEL BEDDING	2,218.89	21,079.49
<b>PART C TERMITE CONTROL</b>					
1000(1)	153.00	sq.m.	SOIL POISONING	89.99	13,769.17
<b>PART D CONCRETE WORKS</b>					
900 (a)	3.60	cu.m.	REINFORCED CONCRETE COLUMN FOOTING	7,614.94	27,413.77
902 (a)	265.30	kg.	REINFORCING STEEL FOR COLUMN FOOTING	74.72	19,822.58
900 (b)	7.10	cu.m.	REINFORCED CONCRETE TIE BEAM & LINTEL BEAM	12,945.35	91,911.99
902 (b)	1,366.154	kg.	REINFORCING STEEL FOR TIE BEAM & LINTEL BEAM	72.27	98,726.25
900 (c)	6.10	cu.m.	REINFORCED CONCRETE COLUMN, PC & STIFFENER	12,293.91	74,992.88
902 (c)	1,950.633	kg.	REINFORCING STEEL FOR COLUMN, PC & STIFFENER	71.73	139,918.48
900 (d)	7.66	cu.m.	REINFORCED CONCRETE BEAMS (RB & LRB)	12,292.48	94,160.38
902 (d)	1,222.699	kg.	REINFORCING STEEL FOR CONCRETE BEAMS (RB & LRB)	71.00	86,811.29
900 (e)	16.98	cu.m.	REINFORCED CONCRETE FLOORING, CORRIDOR & RAMP Note: Elevate finish floor to 0.60m from natural ground	7,374.57	125,220.22
902 (e)	740.222	kg.	REINFORCING STEEL FOR CONCRETE FLOORING, CORRIDOR & RAMP	73.27	54,238.65
900 (f)	1.65	cu.m.	REINFORCED CONCRETE WORKS FOR TWO - UNIT C.R.	18,356.73	30,288.61
902 (f)	219.40	kg.	REINFORCING STEEL FOR TWO - UNIT C.R.	74.50	16,346.45
<b>PART E MASONRY WORKS</b>					
1046	163.29	sq.m.	MASONRY WORKS	1,273.85	208,007.68
<b>PART F FINISHING</b>					
1027 (1)	254.70	sq.m.	CEMENT PLASTER FINISH	254.24	64,754.95
<b>PART G TILEWORKS</b>					
1018 (3)	33.36	sq.m.	CERAMIC TILES (COMFORT ROOMS)	1,493.38	49,819.00
<b>PART H METAL STRUCTURES</b>					
1047	5,195.313	kg.	STRUCTURAL STEEL (ROOF FRAMING, FASCIA & RAMP RAILING)	117.86	612,326.01
1003 (1)	194.21	sq.m.	4.5MM METAL FRAME FIBER CEMENT BOARD	826.12	160,439.84
1051 (5)	4.00	pc.	METAL RAILING (GRABRAIL) FOR PWD COMFORT ROOM	6,447.30	25,789.19
<b>PART I ROOFING WORKS</b>					
1014	209.00	ln.m.	PRE - PAINTED METAL SHEETS	853.28	178,334.67
<b>PART J DOORS AND WINDOWS</b>					
1009 (1)	23.66	sq.m.	GLASS JALOUSIE WINDOW INCLUDING JAMBS (W-1 & W-2)	2,672.73	63,236.86
1010	7.56	sq.m.	WOODEN DOORS W/ DOOR JAMB	5,118.34	38,694.68
1043	3.78	sq.m.	PVC DOORS AND FRAME FOR C.R.	2,600.37	9,829.38
<b>PART K ELECTRICAL WORKS</b>					
1100	219.00	ln.m.	CONDUIT, BOXES AND FITTINGS	56.35	12,341.32
1101	440.00	mts.	WIRES AND WIRING DEVICES	59.27	26,078.33
1102	1.00	set	PANEL BOARD	3,549.52	3,549.52
1103	28.00	set	LIGHTING FIXTURES AND WALL FAN	877.94	24,582.27
<b>PART L PLUMBING WORKS</b>					
1002	6.00	set	PLUMBING (SANTARY LINES, WATERLINES, & FIXTURES):	8,433.06	50,598.33
1002 (26)	11.30	cu.m.	SEPTIC TANK	4,493.51	50,776.62
<b>PART M PAINTING WORKS</b>					
1032 (1)a	621.46	sq.m.	MASONRY PAINTING (INCLUDING FIBER CEMENT BOARD)	144.51	89,809.53
1032 (1)b	78.80	sq.m.	WOODEN PAINTING, STEEL FASCIA, AND RAILING	178.73	14,083.69
<b>PART N CARPENTRY</b>					
1003	2.00	unit	BLACKBOARDS	7,984.25	15,968.50

RECEIVED BY: \_\_\_\_\_  
 DATE: \_\_\_\_\_  
 AMOUNT: P 2,767,749.59  
 1999-0001  
 2021-0046  
 2021-01

**TOTAL ESTIMATED CONTRACT COST: P 2,767,749.59**

**Purpose/Remarks :** Furnishing of Labor, Materials and Equipment for the CONSTRUCTION OF 2-CLASSROOM SCHOOL BUILDING WITH PWD TOILETS AT VALERIANO A. GANAS HIGH SCHOOL at TAMBOAN, CARMEN, BOHOL

Mode of Procurement : **Bidding**

No. of days delivered : **120 Calendar Days**

Place of Delivery : **Project Site**

To be awarded : **By lot**




PROVINCIAL ENGINEER - BOHOL

MARK NO. 1999 / VALID UNTIL 12/31/21

3711-107040x / 2,767,749.59

PSM 2021-01

FELER... BHO

Requested by:	Cash Availability :	Approved by:
Signature  Printed Name <b>CAMILO L. GASATAN</b> Designation Provincial Engineer	Signature  Printed Name <b>EUSTAQUIO A. SOCORIN</b> Designation Provincial Treasurer	Signature  Printed Name <b>HON. ARTHUR C. YAP</b> Designation Governor