

PR No. _____ Date: May 3, 2021
 SAI No. _____ Date: _____
 ALOBS NO. _____ Date: _____

Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
1002 (a)	1.00 lot	Plumbing Works Supply of materials, labor and equipment for Water Lines Using PPR Pipes and Fittings for Dialysis Machine Recycling and Reprocessing including labor for installation, chipping of Masonry Wall, demolition of portion of affected ceiling, excavation works for drain pipe trench, backfilling works and restoration of affected masonry wall, ceiling and painting works using the following materials: > 1"ø PPR Pipes, fittings and gate valves for water supply main pipeline > 3/4"ø PPR Pipes, fittings and gate valves for water supply branch pipelines from main water pipeline to individual Hemodialysis Machine, Handwash Station, Dialyzer Reprocessing machines and bicarbonate mixing room. > 2"ø PVC Blue Pipes and fittings for main drain pipeline to the septic tank > 3/4"ø PPR branch Pipe and fittings from the individual Hemodialysis Machine, and Dialyzer Reprocessing Machine to the main drain pipeline. > 4.5 mm Fiber Cement Board on light metal frames replacement to the ceiling board that will be affected and damaged during installation of pipes. > Retouching of cement plaster and painting works using appropriate paint and color of existing building. > backfilling of trench in the laying of pipelines using the excavated materials.	P 197,236.85	P 197,236.85
1002 (11a)	1.00 unit	Sink for Infectious Dialyzer Processing Supply including installation of Stainless Sink with inside dimensions of L=80cm x W=40cm x D=36cm, complete with fittings and accessories	P 32,025.00	P 32,025.00
SPL 1	1.00 set	Pre-Filtration for RO Dialysis Machine Supply and installation of Pre-Filtration Unit for RO Dialysis machine with the following component: Iron Removal with: 1 unit FRP Tank, 13X54 1 unit Manual Head Carbon 3 bags Activated Media Filter 1 bag Pebbles Filter Carbon Filter: 1 unit FRP Tank, 13X54 1 unit Manual Head Carbon 2 bags Activated Media Filter 1 bag Pebbles Filter Softener Filtration: 1 unit FRP Tank, 13X54 1 unit Manual Head Softener 3 bag Ion Exchange Resin 80 Liters Brine Tank	P 301,875.00	P 301,875.00
SPL 2	1.00 lot	Miscellaneous Works Enclosure for Bicarbonate Mixing Room 10.92 sq.m. - Supply and installation of dry wall partition using 12mm x 4" x 8" Hardiflex Cement Board, double wall, on light gauge vertical & horizontal wall studs using 0.40mm x 50mm x 100mm rectangular tube spaced at 0.60m on center both ways 1 set - Supply and installation of Hollow Core Flush Door, 0.80m x 2.10m using double wall marine plywood, 2" x 6" Kiln dried S4S door jamb, and S4S wooden door frames, complete with Door Knob and 3 1/2" x 3 1/2" Loosepin Hinges Electrical Works 3 set - Supply and Installation of 2-gang three prong Convenience Outlet, 1 unit at the Bicarbonate Mixer Room and 2 units at thereprocessing room including chipping works, restoration of masonry and painting finishes for the affected wall and ceiling 1 unit - Replacement of 100 amperes to 60 Amperes Circuit breaker, single phase, at the R.O. Room Renovaion of Exit Door at the Reprocessing Room 1 set - Renovation of exit door at the reprocessing room into 1.50m width x 2.10 swing door with 2 panels wooden door including demolition/chipping works, supply and installation 2" x 6" Kiln Dried wooden door jambs, door knob, hinges, chain bolt, foot bolt and restoration of affected masonry and painting finishes	P 62,902.22	P 62,902.22
XXXXXXXXXX			TOTAL ESTIMATED CONTRACT COST: P	594,039.08

2021-121
 JR/P/R# _____ RECEIVED BY: *[Signature]* DATE: 5/13/2021
PROVINCIAL PROCUREMENT MANAGEMENT UNIT
 NC-PHO-2021-092
 PB# _____ SC# _____ RSC# _____
 AMOUNT: P 594,039.08 OK AS TO APP# _____

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the
INSTALLATION OF HEMODIALYSIS PLUMBING AND REPROCESSING SYSTEM AND MISCELLANEOUS WORKS
at GARCIA MEMORIAL PROVINCIAL HOSPITAL, TALIBON, BOHOL

Mode of Procurement : **Alternative Mode**
 No. of days delivered : **45 Calendar Days**
 Place of Delivery : **Project Site**
 To be awarded : **By lot**

Requested By: *[Signature]* Cash Availability : _____ Approved by: _____

Signature: *[Signature]* Printed Name: **CAMILO L. GASATAN** Designation: **Provincial Engineer**

Signature: *[Signature]* Printed Name: **EUSTAQUIO A. SOCORIN** Designation: **Provincial Treasurer**

Signature: *[Signature]* Printed Name: **HON. ARTHUR C. YAP** Designation: **Governor**

PROVINCIAL BUDGET OFFICE
PROVINCE OF BOHOL
 INTERNAL USE ONLY