

	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 1.0HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	set	1.00	57,238.72	57,238.72
8	FOR PREPARATION AND PACKAGING AREA				
	1.) 3 in 1 Split Type, Wall Mounted Full DC Inverter Air Conditioning Unit, 0.8HP, Equipped with Anti-molds and bad odors after you turn the unit on & off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230 volts, 1ph, 60 hz	set	1.00	65,260.63	65,260.63
1200 (a)	VENTILLATION SYSTEM				
	Exhaust Fans, 11 Watts, 450 CFM, including duct, pipes, brackets and grills for eave ceiling	sets	69.00	3,384.48	233,529.12
1100	ELECTRICAL WORKS				
	1. Supply & Installation of Panel Boards, Main Breakers, Bed Head unit Panel, Wire Devices & Pipes	assy.	21.00	183,903.58	3,861,975.18
	2. Wires & Cables	m.	28,871.45	65.27	1,884,439.54
	3. Wiring Devices	sets	1361.0	1,213.39	1,651,423.79
1032	PAINTING WORKS				
	a.) Application of Skim Coat for Exterior and Interior Wall and Mezzanine Wall	sq.m.	4,447.47	122.97	546,905.39
	b.) Application of Primer / Sealer for Ceiling	sq.m.	1,558.86	127.22	198,318.17
	c.) Application of Primer / Sealer for Interior Wall, Exterior and Mezzanine Wall	sq.m.	9,446.32	27.16	256,562.05
	d.) Application of Semi-Gloss, Top Coat for Exterior and Interior Wall and Mezzanine Wall	sq.m.	7,756.00	80.24	622,341.44
1202	FIRE PROTECTION FOR MAIN BUILDING	lot	1.00	789,088.12	789,088.12