

	4. 4mm thk. Clear glass fixed Window with Aluminum Frame Powder Coated White finished, 1.95 x 1.20M (4 units)	sq.m.	9.36	2,899.17	27,136.23
	5. 6mm thk. Tempered fixed Window with Aluminum Frame Powder Coated White finished, 1.95 x 1.20M (7 units)	sq.m.	3.36	4,406.75	14,806.68
	6.) Supply and Installation of Aluminum Frame Powder Coated, 6mm thk. Tempered Glass, white finish sliding Window for Laboratory Department	sq.m.	9.36	6,378.20	59,699.95
	7.) Door 2, Double Swing Aluminum Frame, Powdered Coated, White Finish, 6mm thk. Tempered Glass, Heavy Duty Hinges, Lockset, Bottom Pivot, Hinges, concealed flush bolt & handle 1.80 x 2.60 with Transom and 0.80 x 2.60 Fixed Window				
	1.80 x 2.6 Swing Door	sq.m.	9.36	14,781.17	138,351.75
	0.80 x 2.6 Fixed Window	sq.m.	6.24	6,378.19	39,799.91
1020	VINYL FLOOR TILES FINISHES				
	Laying of Homogeneous flooring with Anti-bacterial and Anti-Static, 2.0mm thick Vinyl Sheets Flooring with Self Leveling	sq.m.	1,030.69	2,039.12	2,101,700.59
1035	SUPPLY AND INSTALLATION OF NON-STRUCTURAL MEMBERS				
	Toilet door using Phenolic Board and ½" Østainless Pipe Frame, Stainless hinges, Stainless stand with Escutcheon, Stainless Door Lock and Handle 1.80 x 0.70m (11 units)	sets	11.00	11,305.35	124,358.85
	Toilet partition using rectangular tube powder coated white aluminum frame two panes, using ¼" thk smoked glass, fix glass with Stainless Steel Curtain Rod (8 units) (1.40 x 2.0m)	sets	8.00	17,832.15	142,657.20
1051	RAILINGS				
	Supply and Installation of Staircase Stainless Handrails	sq.m.	23.48	5,088.06	119,467.65
	Supply and Installation of Mezzanine Stainless Railings	m.	47.81	6,802.75	325,239.48