

	3 bags Activated Media Filter				
	1 bag Pebbles Filter				
	Carbon Filter:				
	1 unit FRP Tank, 13 x 54				
	1 unit Manual Head Carbon				
	2 bags Activated Medial Filter				
	1 bag Pebbles Filter				
	Softener Filtration:				
	1 unit FRP Tank, 13 x 54				
	1 unit Manual Head Softener				
	3 bag Ion Exchange Resin				
	80 Liters Brine Tank				
SPL 2	Miscellaneous Works	Lot	1.0	61,750.00	61,750.00
	Enclosure for Bicarbonate Mixing Room				
	10.92 sq.m. - Supply and installation of dry wall partition using 12mm x 4' x 8' Hardiflex Cement Board, double wall, on light gauge vertical & horizontal wall studs using 0.40mm x 50mm x 100mm rectangular tube spaced at 0.60m on center both ways				
	1 set - Supply and installation of Hollow Core Flush Door, 0.80m x 2.10m using double wall marine plywood, 2" x 6" Kiln died S4S door jamb, and S4S wooden door frames, complete with Door Knob and 3 ½" x 3 ½" Loosepin Hinges				
	Electrical Works				
	3 sets - Supply and Installation of 2-gang three prong Convenience Outlet, 1 unit at the Bicarbonate Mixer Room and 2 units at there processing room including chipping works, restoration of masonry and painting finishes for the affected wall and ceiling				
	1 unit - Replacement of 100 amperes to 60 Amperes Circuit breaker, single phase, at the R.O. Room				
	Renovation of Exit Door at				