

903	FORMS & SCAFFOLDINGS(FOR 7 COLUMNS)	BD.FT	546.67	84.98	46,456.02
PART D	MASONRY WORKS				-
1046 (A)	EXTERIOR WALL	SQ.M	70.56	1,211.22	85,463.68
1046 (B)	INTERIOR WALL	SQ.M	41.02	1,082.98	44,423.84
PART E.	FINISHING				-
1027	CEMENT PLASTER FINISH FOR NEW MASONRY WALL	SQ.M	197.27	275.07	54,263.06
PART F.	TILEWORKS				-
1018 (A)	FLOORING GRANITE TILES	SQ.M	44.55	1,574.86	70,160.01
1018 (B)	COMFORT ROOM CERAMIC TILES	SQ.M	31.49	2,041.92	64,300.06
1018 (C)	COUNTER GRANITE SLAB	SQ.M	6.30	9,377.84	59,080.39
PART G.	METAL STRUCTURES				
1047	ROOF FRAMING AND TRUSSES	KG.	1,712.67	106.09	81,697.16
1032 (A-1)	STEEL PAINTING WORKS	LOT	146.83	129.54	19,020.36
PART H.	FIBER CEMENT BOARD, GYPSUM BOARD ON LIGHT METAL FRAME				
1003 (1)E1	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR FIBER CEMENT BOARD CEILING & DRYWALL & SPANDREL EXTERIOR CEILING USING SPANDREL ON LIGHT METAL FRAMES	SQ.M	36.52	873.49	31,899.85
	4.5MM X 4' X 8' HARDIFLEX CEMENT BOARD ON LIGHT GAUGE METAL FRAME SPACED AT 0.60M ON CENTER BOTHWAYS USING 0.80MM X 12MM X 38MM CARRYING CHANNEL, 0.40MM X 19MM X 50MM DOUBLE FURRING ON CELING BOARD JOISTS, 0.40MM X 19MM X 25MM SINGLE FURRING HANGERS AND 0.40MM X 25MM X 25MM WALL ANGLE, INTERIOR CEILING				-
1003 (1)E2	EXTERIOR CEILING USING SPANDREL ON LIGHT METAL FRAMES	SQ.M	65.80	1,516.72	99,800.18