

	0.40MM X 0.110M SPANDREL METAL CEILING BOARD, WHITE, USING 0.40MM X 19MM X 50MM DOUBLE FURRING AND 0.40MM X 25MM X25MM DOUBLE COATED, WHITE, WALL ANGLE WITH AIRVENT SLAT, ROOFING EAVE CEILING				
1003 (2)A1	METAL FRAME & FIBER CEMENT BOARD WALLING	SQ.M	49.85	2,143.88	106,872.42
	12MM X 4' X 8' HARDIFLEX CEMENT BOARD ON LIGHT GAUGE METAL FRAME SPACED AT 0.60M ON CENTER BOTHWAYS USING 0.40MM X 50MM X 100MM RECTANGULAR TUBE VERTICAL AND HORIZONTAL WALL STUDS DRY WALL PARTITION, DOUBLE WALL				
PART I.	ROOFING WORKS				
94	PRE-PAINTED OVEN-BAKED METAL SHEETS	IN.M.	94.20	1,632.70	153,800.34
PART J.	CARPENTRY & JOINERY WORKS				
1003 (4)	CABINETS				-
B.	TRANSACTION/NURSES STATION	SET	1.00	11,638.92	11,638.92
C.	SOILED/CLEAN LINEN CABINET	SET	1.00	17,269.57	17,269.57
A.	BUSINESS AREA COUNTER	SET	1.00	10,962.39	10,962.39
1032 (1)B	CABINET PAINTING WORKS	UNIT	58.56	341.53	20,000.00
PART K.	DOORS AND WINDOWS				
1007	ALUMINUM FRAMED GLASS DOORS	UNIT	9.00	21,833.33	196,499.97
	SUPPLY OF MATERIALS AND LABOR IN THE INSTALLATION OF ALUMINUM FRAMED DOORS:				
	ROLL-UP DOOR SINGLE PANEL 1.50 X 2.20	UNIT	1.0		
	SWING DOOR DOUBLE THROW 2 PANELS 1.85 X 2.10 HA/TEMP	UNIT	1.0		
	SWING DOOR DOUBLE THROW 2 PANELS 1.20 X 2.10 HA/TEMP	UNIT	1.0		
	SWING DOOR DOUBLE THROW SINGLE PANEL 0.90 X 2.10 HA/TEMP	UNIT	1.0		
	SWING DOOR DOUBLE THROW SINGLE PANEL 0.70 X 2.10 HA/TEMP	UNIT	1.0		