

PART L.	ELECTRICAL WORKS				
1100	CONDUIT, BOXES AND FITTINGS	LOT	1.00	179,125.00	179,125.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR ELECTRICAL CONDUIT, BOXES AND FITTINGS USING THE FOLLOWING:				
	1/2" Ø PVC ELECTRICAL CONDUIT PIPE, ORANGE HD, 3M/PC	PC.	777.00		
	1/2" Ø PVC ELECTRICAL CONDUIT ELBOW, 90 DEG.	PC.	52.00		
	1/2" Ø PVC ELECTRICAL CONDUIT MALE ADAPTOR W/ LOCKNUT	PC.	446.00		
	3/4" Ø PVC ELECTRICAL CONDUIT PIPE, ORANGE, HD, 3M/PC	PC.	12.00		
	3/4" Ø PVC ELECTRICAL CONDUIT ELBOW 90 DEG.	PC.	2.00		
	3/4" Ø PVC ELECTRICAL CONDUIT MALE ADAPTOR W/ LOCKNUT	PC.	8.00		
	65MM Ø PVC CONDUIT, HD 180M	PC.	60.00		
	65MM Ø PVC CONDUIT, HD ELBOW	PC.	2.00		
	OCTAGONAL BOX WITH COVER PVC, ORANGE	PC.	83.00		
	2 X 4 UTILITY BOX ORANGE	PC.	86.00		
	PULL BOX, 300MM X 300MM X 100MM STEEL	PC.	4.00		
	3" Ø WEATHER PROOF SERVICE HEAD(ENTRANCE CAP)	PC.	1.00		
1101	WIRES AND WIRING DEVICES	LOT	1.00	875,090.00	875,090.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR ELECTRICAL WIRES AND WIRING DEVICES USING THE FOLLOWING:				-
	2.0 SQ.MM THHN CU, WIRE STRANDED	M.	140.00		-
	3.5 SQ.MM THHN CU, WIRE, STRANDED	M.	1,720.00		-
	5.5 SQ.MM THHN CU, WIRE, STRANDED	M.	870.00		-
	8.0 SQ.MM THHN CU, WIRE, STRANDED	M.	58.00		-
	38 SQ.MM THHN CU, WIRE STRANDED	M.	95.00		-
	22 SQ.MM THHN CU, WIRE STRANDED	M.	95.00		-
	125 SQ.MM THHN CU WIRE STRANDED	M.	150.00		-
	50 SQ.MM TW CU, WIRE STANDED, GROUNDING	M.	50.00		-
	22.0 SQ.MM TW CU, WIRE STRANDED, GROUNDING	M.	15.00		-
	8.0 SQ.MM TW CU WIRE STRANDED GROUNDING	M.	15.00		-
	14 SQ.MM TW CU, WIRE STANDED, GROUNDING	M.	29.00		-
	THREE SPOOL SECONDARY TRACK(PORCELAIN WIRE HOLDER)	M.	2.00		-
	GROUND ROD, 16MM Ø X 8 FT.	M.	2.00		-
	0.16MM X 19MM X 16MM PVC ELECTRICAL INSULATING TAPE	ROLL	66.00		-
	BUTYL RUBBER TAPE NO. 15 NITTO	PC.	12.00		-