

A.	FOR DIALYSIS CENTER	UNIT	4.00	89,020.00	356,080.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR THE INSTALLATION OF DIALYSIS CENTER ROOM AIR-CONDITIONING UNITS INCLUDING PIPING SYSTEM				
	AIRCONDITIONING UNIT, WALL MOUNTED SPLIT TYPE A/C, 3 IN 1 FULL DC INVERTER COMPONENTS-INVERTER COMPRESSOR, INVERTER MODULE AND INVERTER FAN MOTOR; EQUIPPED WITH NANO SILVER AND PHOTOCATALYST FILTER AND ANTI-ALLERGY AGENT FILTER, EASY TO CLEAN PANEL, AUTO RESTART FUNCTION, AUTO PROTECTION MODE WIRELESS REMOTE, 2.0HP COOLING CAPACITY, 230V/1PH/60HZ				
B.	FOR STAFF ROOM	UNIT	1.00	37,200.00	37,200.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR THE INSTALLATION OF STAFF ROOM AIR-CONDITIONING UNITS INCLUDING PIPING SYSTEM				-
	WINDOW TYPE AIRCONDITIONING UNIT, FULL DC INVERTER, COMPACT SIZE, 0.8 HP CAPACITY, DUAL FAN MOTORS, SELF-DIAGNOSE FUNCTION, AION FILTER ECO FRIENDLY REFRIGERANT, HIGH EFFICIENCY RATIO, USER-FRIENDLY REMOTE CONTROL, 230V, 1PH, 60HZ				-
C.	FOR DOCTOR'S ROOM, BUSINESS AREA, WAITING AREA	UNIT	1.00	115,000.00	115,000.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR THE INSTALLATION OF DOCTOR'S ROOM, BUSINESS AREA WAITING AREA AIR-CONDITIONING UNITS INCLUDING PIPING SYSTEM				-
	AIRCONDITIONING UNIT WALL MOUNTED SPLIT TYPE A/C, 3 IN 1 FULL DC INVERTER COMPONENTS-INVERTER COMPRESSOR, INVERTER MODULE AND INVERTER FAN MOTOR; EQUIPPED WITH NANO SILVER AND PHOTOCATALYST FILTER AND ANTI-ALERGY AGENT FILTER, EASY TO CLEAN PANEL, AUTO RESTART FUNCTION, AUTO PROTECTION MODE, WIRELESS REMOTE, 3.0HP COOLING CAPACITY, 230V/1PH/60HZ.				-
1208	FIRE PROTECTION SYSTEM	LOT	1.00	89,000.00	89,000.00
	SUPPLY OF MATERIALS, LABOR AND EQUIPMENT FOR THE INSTALLATION OF FIRE PROTECTION SYSTEM USING THE FOLLOWING:				
	FIRE ALARM PANEL (ADDRESSABLE TYPE)	SET	1.00		
	SMOKE DETECTOR	PCS	10.00		