

A.3	PROJECT BILLBOARD (4' X 8')(TARPAULIN W/ STANDARD BILLBOARD MARKINGS)	UNIT	1.00	3,607.62	3,607.62
A.4	SAFETY AND HEALTH	LOT	1.00	18,064.67	18,064.67
PART B	WATER SOURCE DEVELOPMENT				-
803(1)	STRUCTURAL EXCAVATION(AT SPRING BOX-3 UNITS)	CU.M	18.84	1,300.16	24,495.01
804(1)	EMBANKMENT	CU.M	5.76	650.08	3,744.46
804(4)	GRAVEL FILL	CU.M	14.88	2,606.56	38,785.61
900(1)	REINFORCED CONCRETE FOR WALL FOOTING	CU.M	3.84	8,145.51	31,278.76
902(1)	REINFORCING STEEL FOR WALL FOOTING	KG.	269.45	81.26	21,895.51
900(1)	REINFORCED CONCRETE FOR RC WALL	CU.M	3.84	8,145.51	31,278.76
902(1)	REINFORCING STEEL FOR RC WALL	KG.	1,022.76	81.26	83,109.48
900(1)	REINFORCED CONCRETE FOR SPRING BOX (2.0M X 1.5M X 1.10M X 3 UNITS)	CU.M	3.69	78.38	289.22
902(1)	REINFORCING STEEL FOR SPRING BOX(2.0M X 1.5M X 1.10M X 3 UNITS)	KG.	415.50	81.26	33,763.53
903	FORMS & SCAFFOLDINGS	BD.FT	433.33	91.98	39,857.69
PART C	TRANSMISSION LINES AND WATER STORAGE FACILITIES				-
803(1)	STRUCTURAL EXCAVATION AT SHED	CU.M	3.84	1,390.17	5,338.25
900(1)	REINFORCED CONCRETE	CU.M	10.77	8,027.02	86,451.01
	TO FOOTING	CU.M	0.72		
	TO PEDESTAL	CU.M	0.28		
	TO FLOORING	CU.M	8.98		
	TO ZOCALO	CU.M	0.67		
	TO LINTEL BEAM	CU.M	0.13		
902(1)	REINFORCING STEEL	KG.	270.19	81.26	21,955.64
	TO FOOTING	KG.	42.62		
	TO PEDESTAL	KG.	72.21		
	TO FLOORING	KG.	118.38		
	TO ZOCALO	KG.	18.50		
	TO LINTEL BEAM	KG.	18.50		
1047	STRUCTURAL STEEL	KG.	1,006.35	130.33	131,157.60