Provincial Agriculturist

Division: Admin Division
Section:

PR No. _____ Date _____
SAI No. _____ Date: September 23, 2021
OB R No. _____ Date: _____

Item No.	Quantity	Unit of Issue	Item Description	Estimated Unit Cost	Estimated Total Cost
1.	1	Set	3-in-1 Full DC Inverter Wall Mounted Split Type Airconditioning Unit (Three DC Inverter Components – Inverter Compressor, Inverter Module, and Inverter Fan Motor), power savings of up to 65%, equipped with anti-mold and cleaning function that purifies the air by eliminating molds and bad odors after you turn the unit on and off, also equipped with Nano Silver and Photocatalyst filter and PM 2.5 filter, 3D Movement Swing Blades, 2.0 HP cooling capacity, wireless remote, 230v, 1ph, 60hz. Compressor warranty: 5 years	₱ 52,800.00	₱ 52,800.0
			Airconditioning Equipment Support, Drains, Circuit Breakers, Wires, Tapes & Accessories		
	1	Pc	Service Circuit Breaker, with enclosure	1,200.00	1,200.00
	4	Meters	# 10 AWG THHN PHILFLEX	50.00	200.00
	25	Meters	Royal cord, 4 x # 14	120.00	3,000.00
	6	Length	PVC Pipe, blue, ¾"	125.00	750.00
	4	Pc	PVC Elbow, ¾"	20.00	80.00
	6	Pc	Expansion Shield with Lag Screw	90.00	540.00
	2	Pc	Silver Rod	80.00	160.00
	25	Pcs	Welding Rod	10.00	250.00
	4	Pcs	Bolts, nuts and washers	15.00	60.00
	1	Length	Angular Bar 11/2" x 11/2" x 3/16" x 20"	950.00	950.00
			Aircon Piping System		
	79	Ft	5/8" dia. Refrigerant pipe, soft drawn	90.00	7,110.00
	79	Ft	¼" dia. Refrigerant pipe, soft drawn	30.00	2,370.00
	14	Length	5/8" x ¾" x 6' rubber insulation Superlon	220.00	3,080.00
	14	Length	¼" x 3/8" x 6' rubber insulation Superlon	45.00	630.00
	1	Roll	Polyethylene Tape	850.00	850.00
	5	Pcs	Copper elbows, 5/8	45.00	225.00
	5	Pcs	Copper elbows, ¼	25.00	125.00
	0.5	Tnk	Nitrogen	1,200.00	600.00
	2	Tnk	Mapp Gas	850.00	1,700.00
	0.5	Tnk	Refrigerant R410A	6,890.00	3,445.00
			Labor Cost (Installation including wall cutting and bracket fabrication)		9,500.00
			x-x-x-x-x		
			TOTAL		**₱ 89,625.00**

JA/PA # 0843 RECEIVED BY: PROVINCIAL PROCUREMENT MANAGEMENT UNIT DATE
PR # ___ DC # 89,625 SC # 004-0016 RSC # ___
AMOUNT: ___ OKAS TO APP:

PROVINCIAL BUDGET OFFICE
PROVINCE OF BOHOL
CONTROL NO. 1592 REC'D BY: DATE: 9/20/21
EARMARK NO. 2007 VALID UNTIL 12/31/2021
EXPENSE CODE 8711/1070500 AMOUNT 89,625
FUND SOURCE 2016-0400 CONTROLLER DATE 9/28/2021
PETER PO S. M. RETUTAL, CPA
BY AUTHORITY OF THE GOVERNOR:

Purpose: For use at the room of the office head

Time Delivery: 20 working days upon receipt of the NTP/PO
Place of Delivery: OPA Office
Mode: Alternative mode of procurement thru shopping under 52.1a

	Requested by:	Cash Availability:	Approved by:
Signature			ATTY. JOSE MARIE N. POBLETE DULY AUTHORIZED REPRESENTATIVE
Printed Name	**LARRY M. PAMUGAS, Ph.D.**	**EUSTAQUIO A. SOCORIN**	**ATTY. ARTHUR C. YAP**
Designation	Asst. Provincial Agriculturist 09/23/2021	Provincial Treasurer	Governor

3