

A.4	SAFETY AND HEALTH	LOT	1.00	7,920.00	7,920.00
PART B	CONSTRUCTION OF EXTENSION BUILDING				-
801	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LOT	1.00	25,200.00	25,200.00
803(1)	STRUCTURAL EXCAVATION	CU.M.	31.26	1,140.00	35,636.40
804 (1)	EMBANKMENT	CU.M.	125.00	670.50	83,812.50
900 (1)	REINFORCED CONCRETE FOR COLUMN FOOTING	CU.M.	4.95	7,759.00	38,407.05
902 (1)	REINFORCING STEEL FOR COLUMN FOOTING	KG.	388.68	86.00	33,426.48
900 (1)	REINFORCED CONCRETE FOR COLUMN	CU.M.	2.51	7,892.00	19,808.92
902 (1)	REINFORCING STEEL FOR COLUMN	KG.	453.64	87.00	39,466.68
900 (1)	REINFORCED CONCRETE FOR WALL FOOTING	CU.M.	3.21	7,880.00	25,294.80
902 (1)	REINFORCING STEEL FOR WALL FOOTING	KG.	158.33	86.00	13,616.38
900 (1)	REINFORCED CONCRETE FOR WALL STIFFENER & CONCRETE COPING	CU.M.	0.27	13,043.00	3,521.61
902 (1)	REINFORCING STEEL FOR WALL STIFFENER & CONCRETE COPING	KG.	52.09	87.00	4,531.83
900 (1)	REINFORCED CONCRETE FOR SLAB ON GRADE WITH STAIRS, RAMP & COUNTERS	CU.M.	15.08	7,532.00	113,582.56
902 (1)	REINFORCING STEEL FOR SLAB ON GRADE WITH STAIRS, RAMP & COUNTERS	KG.	392.12	87.00	34,114.44
1047 (1)	STEEL WORKS	KG.	3,051.50	131.00	399,746.50
1047 (9)	STAINLESS STEEL PIPE	IN.M.	87.10	2,069.00	180,209.90
1014 (1)b2	PRE-PAINTED METAL SHEETS	SQ.M.	172.00	1,243.00	213,796.00
1046	MASONRY WORKS	SQ.M.	82.94	874.00	72,489.56
1027 (1)	CEMENT PLASTER FINISH	SQ.M.	102.01	242.00	24,686.42
1018	TILEWORKS	SQ.M.	205.02	1,500.00	307,530.00
1018 (c)	COUNTER GRANITE SLAB	SQ.M.	4.32	5,880.00	25,401.60
1003 (1)a1	FIBER CEMENT BOARD AND SPANDREL CEILING ON LIGHT METAL FRAME	SQ.M.	55.21	1,279.00	70,613.59