

	Supply and Installation of:				-
	23.10 sq.m. - 4.5mm thk x 4' x 8' Hardiflex Cement Board on light gauge metal frame spaced @0.60m O.C.B.W., using 0.80mm x 12mm x 38mm carrying channel, 0.40mmx19mmx50mm double furring on ceiling board joints, 0.40mmx19mmx25mm single furring hangers and 0.40mmx25mmx25mm wall angle, for comfort rooms (Common and PWD)				-
	18.54 sq.m. - 4.5mm thk x 4' x 8' Hardiflex Cement Board on vertical & horizontal wall studs spaced @ 0.60m O.C.B.W. Using 0.40mm x 50mm x 100mm rectangular tube, double wall, above existing masonry wall for Common Comfort room				-
	13.57 sq.m. - 0.40mm x 0.110m Metal Ceiling Board, Spandrel, white, using 0.40mm x 19mm x 50mm double furring and 0.40mm x 38mm x 38mm powder coated white wall angle				-
1003 (2)	CARPENTRY AND JOINERY WORKS FOR WALL PARTITION AND OPEN SHELVES	bd.ft	136.00	264.00	35,904.00
1003 (22)	COMPARTMENT FOR COMFORT ROOMS	SQ.M.	15.87	6,438.00	102,171.06
1008 (1).a	ALUMINUM SLIDING WINDOW	SQ.M.	7.28	5,899.00	42,944.72
	Supply and Installation of:				-
	4 set - Open Back Powder Coated, White, Aluminum Frame, Two Panes using 1/4" thk clear glass, Sliding window, 1.50m x 0.60m				-
	1 set - Open Back Powder Coated, White, Aluminum Frame, Four Panes using powder coated white fixed louver, 3.68m x 1.0m				-
1010 (2)	PVC DOORS	SET	4.00	5,152.00	20,608.00
1032 (1)a	PAINTING FOR MASONRY WALL AND DRYWALL PARTITION	SQ.M.	160.88	261.00	41,989.68
1032 (1)b	PAINTING FOR CEILING	SQ.M.	23.10	206.00	4,758.60
1032 (2)	PAINTING FOR OPEN SHELVES/WALL PARTITIONS	SQ.M.	51.30	280.00	14,364.00
1032 (1)c	PAINTING FOR STEEL	SQ.M.	351.25	157.00	55,146.25
1039	ALUMINUM CLADDING	SQ.M.	14.40	3,203.00	46,123.20
	6mm Hyperbond Aluminum Cladding, Green with 1"x 1" Aluminum Frame spaced @ 0.60m on center bothways				-
903	FORMS and SCAFFOLDINGS	bd.ft.	725.33	51.00	36,991.83
<b>PART C</b>	<b>IMPROVEMENT OF OLD HR BUILDING</b>				-
C.1	CRISIS INSTRUCTION DIVISION				-