

1003	RECORD ROOM'S FILING CABINET		43.02	6,692.00	287,889.84
C.2	MAIN OFFICE: ADH, CONFERENCE, SOCIAL DEVELOPMENT, ADMIN DIVISION AND DEPARTMENT HEAD				-
801	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	SQ.M.	41.84	439.00	18,367.76
1008 (1).a	ALUMINUM SLIDING WINDOW	SQ.M.	34.42	5,475.00	188,449.50
	1 set - Open Back/Rectangular Tube Powder Coated, White, Aluminum Frame with Transom, Two Panes using 1/4" thk clear glass, Double Swing, Double Throw Door with Ryobi Door Closer, 2.00m x 2.60m, and open back/rectangular tube powder coated, white, Aluminum frame with Transom, two panes using 1/4" thick clear glass, fixed window, 2.12m x 2.60m, Total area is 10.712 sq.m., Department Head Office Entrance Door				-
	1 set - Open Back Powder Coated, White, Aluminum Frame, with Transom, Three Panes using 1/4" thk clear glass, Fixed Window, L-type, 2.62m x 2.60m, Department Head Office				-
	1 set - Open Back/Rectangular Tube Powder Coated, White, Aluminum Frame with Transom, Single Pane using 1/4" thk clear glass, Single Swing, Double Throw Door with Ryobi Door Closer, 0.80m x 2.60m, and open back/rectangular tube powder coated, white, Aluminum frame with Transom, two panes using 1/4" thick clear glass, fixed window, 1.92m x 2.60m, Assistant Department Head				-
	1 set - Open Back Powder Coated, White, Aluminum Frame, with Transom, Four Panes using 1/4" thk clear glass, Fixed Window, 3.78m x 2.60m				-
1003	LOW WALL PARTITION	SQ.M.	39.96	5,323.00	212,707.08
1111	CABLE TRENCH	SQ.M.	26.72	2,100.00	56,112.00
PART D	ELECTRICAL WORKS				-
1100	CONDUIT, BOXES AND FITTINGS	LOT	1.00	43,312.50	43,312.50
1101	WIRES AND WIRING DEVICES	M.	1,428.00	200.00	285,600.00
1102	PANEL BOARD	SET	2.00	35,958.00	71,916.00
1103	LIGHTING FIXTURES and EXHAUST FAN	SET	28.00	1,820.00	50,960.00
1105	NETWORK CABLING SYSTEM	LOT	1.00	161,500.00	161,500.00
1106	CCTV SYSTEM	LOT	1.00	27,750.00	27,750.00
PART E	PLUMBING WORKS				-
1002	PLUMBING	LOT	1.00	215,200.00	215,200.00
SPL	CONSTRUCTION OF CATCH BASIN	SET	6.00	9,600.00	57,600.00