

804(4)	GRAVEL BEDDING	CU.M.	19.00	2,321.55	44,109.45
PART C	TERMITE CONTROL				-
1000(1)	SOIL POISONING	SQ.M.	306.00	90.00	27,540.00
PART D	CONCRETE WORKS				-
900 (a)	REINFORCED CONCRETE COLUMN FOOTING	CU.M.	6.48	8,374.00	54,263.52
902 (a)	REINFORCING STEEL FOR COLUMN FOOTING	KG.	663.24	86.00	57,038.64
900(b)	REINFORCED CONCRETE TIE BEAM & LINTEL BEAM	CU.M.	14.36	14,515.00	208,435.40
902(b)	REINFORCING STEEL FOR TIE BEAM & LINTEL BEAM	KG.	2,732.308	83.75	228,830.80
900(c)	REINFORCED CONCRETE COLUMN, PC & STIFFENER	CU.M.	11.04	13,959.00	154,107.36
902(c)	REINFORCING STEEL FOR COLUMN, PC & STIFFENER	KG.	3,664.395	84.50	309,641.38
900(d)	REINFORCED CONCRETE BEAMS (RB & LRB)	CU.M.	14.06	14,535.00	204,362.10
902(d)	REINFORCING STEEL FOR CONCRETE BEAMS (RB & LRB)	KG.	2,445.398	82.00	200,522.64
900(e)	REINFORCED CONCRETE FLOORING , CORRIDOR & (2 UNITS STAIR)	CU.M.	34.22	8,159.00	279,200.98
902(e)	REINFORCING STEEL FOR CONCRETE FLOORING , CORRIDOR & (2 UNITS STAIR)	KG.	1,828.802	124.00	226,771.45
900(f)	REINFORCED CONCRETE WORKS FOR FOUR-UNIT C.R.	CU.M.	3.31	18,734.50	62,011.20
902(f)	REINFORCING STEEL FOR FOUR-UNIT C.R.	KG.	438.80	88.00	38,614.40
900(g)	REINFORCED CONCRETE WALL FOOTING (ON RETAINING WALL)	CU.M.	6.76	8,994.00	60,799.44
902(g)	REINFORCING STEEL FOR WALL FOOTING (ON RETAINING WALL)	KG.	146.12	83.00	12,127.96
PART E	MASONRY WORKS				-
1046	MASONRY WORKS	SQ.M.	353.38	1,219.75	431,035.26
PART F	FINISHING				-
1027(1)	CEMENT PLASTER FINISH	SQ.M.	554.58	256.00	141,972.48
PART G	TILEWORKS				-
1018 (3)	CERAMIC TILES (COMFORT ROOMS)	SQ.M.	66.72	1,484.00	99,012.48
PART H	METAL STRUCTURES				-
1047	STRUCTURAL STEEL (ROOF FRAMING, FASCIA & STAIR RAILING)	KG.	10,390.625	124.50	1,293,632.81
1003 (1)	4.5MM METAL FRAME FIBER CEMENT BOARD	SQ.M.	388.42	854.00	331,710.68
1051 (5)	METAL RAILING (GRABRAIL) FOR PWD COMFORT ROOM	PC.	8.00	6,290.00	50,320.00
PART I	ROOFING WORKS				-
1014	PRE-PAINTED METAL SHEETS	IN.M.	421.00	864.91	364,127.11
PART J	DOORS AND WINDOWS				-