

PART B.	CIVIL WORKS				
800(2)	Clearing and Grubbing	cu.m	150.0	26.38	3,957.00
803	Structure Excavation	cu.m	135.0	923.75	124,706.25
804(a)	Backfilling and Compaction	cu.m	50.0	430.39	21,519.50
804(b)	Gravel Bedding	cu.m	9.4	2,818.69	26,495.69
901	Plain/Lean Concrete (Fc'=17.50Mpa)	cu.m	5.1	7,569.61	38,605.01
900	Reinforced Concrete (Fc'=24.5Mpa)				
900(a)	Reinforced Concrete Bottom Slab	cu.m	9.0	9,241.85	83,176.65
902(a)	Reinforcing Steel for Bottom Slab	kg.	948.38	78.92	74,846.15
900(b)	Reinforced Concrete Shear Wall	cu.m	28.0	9,113.95	255,190.60
902(b)	Reinforcing Steel for Concrete Shear Wall	kg.	3,063.60	78.99	241,993.76
900(C)	Reinforced Concrete Suspended Slab (Mid Slab)	cu.m	2.20	9,030.56	19,867.23
902(C)	Reinforcing Steel for Concrete Slab (Mid Slab)	kg.	207.79	91.78	19,070.97
900(D)	Reinforced Concrete Floor Slab	cu.m	1.9	9,095.31	17,281.09
902(D)	Reinforcing Steel for Floor Slab	kg.	154.51	82.79	12,791.88
900(E)	Reinforced Concrete Roof Beam and Wall Footing Tie Beam	cu.m	1.6	9,468.83	15,150.13
902(E)	Reinforcing Steel for Roof Beam and Wall Footing Tie Beam	kg.	245.28	83.92	20,583.90
900(F)	Reinforced Concrete Column Footing	cu.m	1.2	9,082.47	10,898.96
902(F)	Reinforcing Steel for Column Footing	kg.	165.17	83.90	13,857.76