

1046	MASONRY WORKS	SQ.M	12.54	959.50	12,032.13
1027 (1)	CEMENT PLASTER FINISH	SQ.M	25.08	260.70	6,538.36
SPL- 10	WATERPROOFING	SQ.M	17.33	937.00	16,238.21
1018	TILEWORKS	SQ.M	467.92	1,369.00	640,582.48
1018 (C)	COUNTER GRANITE SLAB	SQ.M	5.39	6,447.00	34,749.33
1003 (1)a1	FIBER CEMENT BOARD AND SPANDREL CEILING ON LIGHT METAL FRAME	SQ.M	613.55	1,242.00	762,029.10
	Supply and Installation of:				-
	426.12 sq.m. - 4.5mm thk.x 4'x 8' Hardiflex Cement Board on light gauge metal frame spaced @0.60m O.C.B.W.,using 0.80mm x 12mm x 38mm carrying channel, 0.40mmx19mmx50mm double furring on ceiling board joints, 0.40mmx19mmx25mm single furring hangers and 0.40mmx25mmx25mm wall angle, for Interior Ceiling				-
	187.43 sq.m. - 12mm thk x 4' x 8' Hardiflex Cement Board on vertical & horizontal wall studs spaced @ 0.60m O.C.B.W., drywall partition double wall using 0.40mm x 50mm x 100mm rectangular tube for interior wall partition				-
1010 (2)b	WOODEN DOORS	BD.FT	514.00	270.50	139,037.00
1010 (2)	PVC DOORS	SET	4.00	5,167.00	20,668.00
1032 (1)a	PAINTING FOR MASONRY WALL AND DRYWALL PARTITION	SQ.M	387.40	223.50	86,583.90
1032 (1)b	PAINTING FOR CEILING	SQ.M	426.12	150.00	63,918.00
1032 (1)c	PAINTING FOR WOODEN DOORS, DOOR JAMB and DOOR FRAME	SQ.M	65.64	336.00	22,055.04
PART C.	ELECTRICAL WORKS				-
1100	CONDUIT, BOXES AND FITTINGS	LOT	1.00	50,359.00	50,359.00
1101	WIRES AND WIRING DEVICES	LOT	1,793.00	98.40	176,431.20
1103	LIGHTING FIXTURES AND EXHAUST FAN	SET	40.00	2,200.50	88,020.00