

1006	STEEL DOORS AND FRAMES	SETS	1.0	5,025.00	5,025.00
1008	ALUMINUM FRAMED GLASS WINDOWS	UNITS	2.0	9,860.00	19,720.00
	SUPPLY AND INSTALLATION OF:				
	W1-1.80mW X 1.0mH, 3 PANELS OF SLIDING GLASS IN ANALOK ALUMINUM FRAME				
	W2-1.80mW X 0.6mH, 3 PANELS OF SLIDING GLASS IN ANALOK ALUMINUM FRAME				
1010	WOODEN DOORS AND DOOR JAMB	UNITS	2.0	9,960.00	19,920.00
1011	ROLL-UP DOORS	SQ.M.	6.58	2,900.00	19,082.00
1018 (C)	COUNTER GRANITE SLAB	SQ.M.	3.21	10,300.00	33,063.00
1032 (A-1)	PAINTING WORKS FOR CONCRETE WALL	SQ.M.	118.98	396.00	47,116.08
1032 (B-1)	PAINTING WORKS OF CEILING	SQ.M.	78.86	265.00	20,897.90
1032 (C-1)	PAINTING FOR SHELVES, DRAWER AND TABLE	SQ.M.	72.58	265.00	19,233.70
1032 (D-1)	PAINTING FOR STEEL	SQ.M.	128.73	144.00	18,537.12
<b>PART E.</b>	<b>ELECTRICAL WORKS</b>				
1100	CONDUIT, BOXES AND FITTINGS	LOT	1.0	17,425.00	17,425.00
1101	WIRES & WIRING DEVICES	M.	303.0	98.26	29,772.78
1102 (1)	PANEL BOARD WITH MAIN & BRANCH BREAKERS	SET	1.0	12,825.00	12,825.00
1103	LIGHTING FIXTURES	LOT	1.0	21,750.00	21,750.00
<b>PART F.</b>	<b>MECHANICAL WORKS</b>				
1200	AIR-CONDITIONING AND VENTALATING SYSTEM	SET	2.0	22,040.00	44,080.00
	1 SET AIRCONDITIONING UNIT, 1 HP WINDOW TYPE, INVERTER, 1PH 230V				