

10, m

F - PR - 2022 - 626

PURCHASE REQUEST

Province of Bohol

#01

3/21/22

(14) 3/21

Department : Provincial Engineer's Office	PR No. _____	Date : March 9, 2022
Section :	SAI No. _____	Date : _____
	ALOBS NO. _____	Date : _____

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
A.1.1(3)	1.00	LS	Construction of Field Office for the Engineer	P 22,629.76	P 22,629.76
B.4(1)	0.30	km.	Construction Survey and Staking	P 40,265.08	P 12,079.52
B.5	1.00	each	Project Billboard / Signboard (8' x 8')	P 8,171.73	P 8,171.73
B.7	1.00	L.S.	Occupational Safety and Health Program	P 6,836.40	P 6,836.40
B.9	1.00	L.S.	Mobilization /Demobilization	P 57,689.10	P 57,689.10
100(1)	1,200.00	sq.m	Clearing & Grubbing	P 21.42	P 25,705.10
101(4)a2	8.00	l.m.	Removal of Actual Structures/Obstruction, (760mmØ RCPC)	P 597.22	P 4,777.78
102(2)	816.46	cu.m.	Surplus Common Excavation (roadway & side ditch)	P 190.92	P 155,881.03
103(6)a	49.26	cu.m.	Pipe Culverts and Drain Excavation (Common Soil)	P 306.25	P 15,084.93
104(2)a	62.21	cu.m.	Embankment from Roadway Excavation	P 304.82	P 18,962.69
105(1)a	1,265.36	sq.m.	Subgrade Preparation (Common Material)	P 21.17	P 26,793.13
200(1)	711.00	cu.m.	Aggregate Subbase Course, 0.20m.thk. (includes shouldering)	P 1,133.53	P 805,938.05
311(1)c1	1,830.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	P 1,818.49	P 3,327,832.21
500(1)a3	9.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC	P 6,134.40	P 55,209.59
506(1)	17.04	cu.m.	Stone Masonry (Lined Canal, Headwalls, Aprons, Wingwalls & Parapet)	P 4,920.16	P 83,854.78
624(1)a1	5.00	set	Single Arm Post (6m.), Solar LED Street Light, 50 watts	P 72,257.93	P 361,289.67
SPL	4.00	each	PEO RROW Marker	P 2,816.13	P 11,264.51
TOTAL				P	5,000,000.00

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the Concreting of Concreting of San Miguel - Tomoc - Getafe Road

Road I.D. No. : 07BOH065-20%DF-2022-009

Mode of Procurement : Bidding

No. of days delivered : 60

Place of Delivery : Project Site

To be awarded : By lot

Handwritten notes: PR INF - 2022 - 0011, A-2022-0011, A-2022-0011

Requested By:	Cash Availability :	Approved By:
<i>(Signature)</i>	A-2022-0011	<i>(Signature)</i>
Signature		
Printed Name	CAMILO L. GASATAN	EUSTAQUIO A. SOCORIN
Designation	Provincial Engineer	Provincial Treasurer
		ENRICO ARISTOTLE C. AUMENTAL GOVERNOR

PROVINCIAL BUDGET OFFICE
PROVINCE OF BOHOL

INTERNAL NO. 724 RECD 3/18/22

VALID UNTIL 12/31/2022

9908 - 9000-01-08-85 / 10703016 - 5,000,000 -

2021-0701-101 DF / 85 3/18/2022

PETER ROSSM RETUTALON
- BMO

CHARGED TO
2020 PR OF 2021

DATE 3/18/22

INTERNAL CONTROL DIVISION