

PURCHASE REQUEST

Province of Bohol

Department : Provincial Engineer's Office	PR No. _____	Date : May 31, 2022
Section : _____	SAI No. _____	Date : _____
	ALOBS NO. _____	Date : _____

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
A.1.1(3)	1.00	LS	Construction of Field Office for the Engineer ✓	P 21,300.91	P 21,300.91
B.4(1)	0.50	km.	Construction Survey and Staking ✓	P 39,532.98	P 19,766.49
B.5	1.00	each	Project Billboard / Signboard (8' x 8') ✓	P 7,544.98	P 7,544.98
B.7	1.00	L.S.	Occupational Safety and Health Program ✓	P 14,423.27	P 14,423.27
B.9	1.00	L.S.	Mobilization /Demobilization ✓	P 98,455.35	P 98,455.35
100(1)	2,000.00	sq.m.	Clearing & Grubbing ✓	P 20.56	P 41,128.16
101(4)a1	13.00	l.m.	Removal of Actual Structures/Obstruction. (610mmØ RCPC) ✓	P 477.78	P 6,211.12
102(2)	691.50	cu.m.	Surplus Common Excavation (roadway & side ditch) ✓	P 183.29	P 126,742.74
103(1)a	25.30	cu.m.	Structure Excavation (Common Soil) ✓	P 294.00	P 7,438.19
103(6)a	82.10	cu.m.	Pipe Culverts and Drain Excavation (Common Soil) ✓	P 294.00	P 24,137.38
104(2)a	29.40	cu.m.	Embankment from Roadway Excavation ✓	P 292.65	P 8,603.80
105(1)a	2,734.50	sq.m.	Subgrade Preparation (Common Material) ✓	P 20.33	P 55,585.19
200(1)	1,069.10	cu.m.	Aggregate Subbase Course, 0.20m.thk. (includes shouldering) ✓	P 1,117.98	P 1,195,230.11
311(1)c1	2,500.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days ✓	P 1,855.15	P 4,637,870.67
500(1)a3	16.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC ✓	P 6,132.88	P 98,126.03
505(2)a	59.50	cu.m.	Grouted Riprap, Class A (Slope Protection) ✓	P 4,343.77	P 258,454.45
506(1)	46.90	cu.m.	Stone Masonry (Headwalls, Aprons, Wingwalls) ✓	P 5,398.87	P 253,207.20
612(1)	125.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - White ✓	P 954.31	P 119,288.43
624(1)a1	7.00	set	Single Arm Post (6m.), Solar LED Street Light, 50 watts ✓	P 69,118.84	P 483,831.89
SPL	4.00	each	PEO RROW Marker ✓	P 2,557.28	P 10,229.14
TOTAL				P	7,487,575.50

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the Concreting of Pitogo - Aguing Road, CPG.

Road I.D. No. : 07 BOH 083 - 20% DF - 2022-013




Mode of Procurement : Bidding

No. of days delivered : 120

Place of Delivery : Project Site

To be awarded : By lot

RECEIVED: *[Signature]* DATE: 8/4/22
 PROVINCIAL BUDGET OFFICE - MANAGEMENT UNIT
 AMOUNT: ₱7,487,575.50 - 50% - NBO # _____
 CRAS TO APP.

Requested By:	Cash Availability :	Approved by:
Signature  Printed Name CAMILO L. GASATAN Designation Provincial Engineer	 EUSTAQUIO A. SOCORIN Provincial Treasurer	 ERICO ARISTOTLE G. AUMENTADO GOVERNOR

CHARGED TO.

20% DF 09/2022

PROVINCIAL BUDGET OFFICE

PROVINCE OF BOHOL

CONTROL NO. 1039 REC'D BY *[Signature]* DATE 6/8/22

VALID UNTIL 12/31/2022

AMOUNT ₱ 7,487,575.50

DATE 6/6/2022

S

B