

PURCHASE REQUEST

Province of Bohol

#01 F. PR-2022-427
2/21/22

Department : Provincial Engineer's Office

PR No. 2/21/22 Date: February 16, 2022

Section :

SAI No. _____ Date: _____

ALOBS NO. _____ Date: _____

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount	
A.1.1(3)	1.00	LS	Construction of Field Office for the Engineer	22,629.76	22,629.76	
B.4(1)	0.25	Km.	Construction survey and staking	40,265.08	10,066.27	
B.5	1.00	each	Project Billboard / Signboard (8' x 8')	8,171.73	8,171.73	
B.7(2)	1.00	LS	Occupational Safety and Health Program	14,123.93	14,123.93	
B.9	1.00	L.S.	Mobilization / Demobilization	51,677.33	51,677.33	
100(1)	1,101.00	sq.m.	Clearing & Grubbing (with Stripping)	21.42	23,584.43	
102(2)	253.00	cu.m.	Roadway Excavation (Surplus Common)	190.92	48,303.68	
104(1)a	135.30	cu.m.	Embankment from Roadway Excavation (Common Soil)	304.84	41,244.81	
105(1)a	1,222.00	sq.m.	Subgrade Preparation (Common Material)	21.17	25,875.05	
200 (1)	554.00	cu.m.	Aggregate Subbase Course (t=0.20m.)	1,164.56	645,166.38	
311(1)c1	1,492.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	1,788.12	2,667,868.98	
500 (1) a3	3.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC	6,118.30	18,354.89	
505(2)a	102.00	cu.m.	Grouted Riprap, Class A (Slope Protection)	4,056.06	413,717.94	
506(1)	74.60	cu.m.	Stone Masonry (parapets, headwalls, aprons, & wingwalls)	4,892.62	364,989.62	
605(1)a1	2.00	each	Warning Signs, (60cm triangle)	13,637.72	27,275.44	
605(1)b2	4.00	each	Warning Signs, (75cm triangle)	14,136.47	56,545.87	
605(6)e2	3.00	each	Hazard Markers (Chevron Signs), 600mm x 800mm	18,695.04	56,085.12	
612(1)	54.43	sq.m.	Reflectorized Thermoplastic Pavement Markings (white)	994.07	54,107.49	
612(2)	3.41	sq.m.	Reflectorized Thermoplastic Pavement Markings (yellow)	1,018.95	3,474.62	
624(1)a1	6.00	each	Single Arm Post (8m), with Street Light, LED, 50W	72,237.74	433,426.46	
SPL	4.00	each	PEO RROW Marker	2,809.68	11,238.71	
TOTAL					P	4,997,928.50

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the Concreting of Pob. (Catigbian) - Rizal - Causwagan Sur (San Isidro) Road, Catigbian, Bohol.

Mode of Procurement : Bidding

No. of days delivered : 60 CD

Place of Delivery : Project Site

To be awarded : By lot

2020 MF-01-2027
INTERNAL CONTROL DIVISION

	Requested By:	Cash Availability:	BY AUTHORITY OF THE GOVERNOR
Signature			
Printed Name	CAMILO L. GASATAN	EUSTAQUIO A. SOCORIN	ATTY. KATHRYN P. D. PIOQUINTO
Designation	Provincial Engineer	Provincial Treasurer	PROVINCIAL ADMINISTRATOR ARTHUR C. YAP Governor