

PURCHASE REQUEST

Province of Bohol

Department : **Provincial Engineer's Office**



Section :

PR No. _____ Date : **May 5, 2022**
 SAI No. _____ Date : _____
 ALOBS NO. _____ Date : _____

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
A.1.1(3)	1.00	LS	Construction of Field Office for the Engineer	P 22,218.31	P 22,218.31
B.4(1)	0.60	km.	Construction Survey and Staking	P 39,532.98	P 23,635.19
B.5	1.00	each	Project Billboard / Signboard (8' x 8')	P 7,844.86	P 7,844.86
B.7	1.00	L.S.	Occupational Safety and Health Program	P 19,744.34	P 19,744.34
B.9	1.00	L.S.	Mobilization /Demobilization	P 60,837.53	P 60,837.53
100(1)	2,391.00	sq.m.	Clearing & Grubbing	P 20.56	P 49,168.72
101(4)a1	8.00	l.m.	Removal of Actual Structures/Obstruction. (610mmØ RCPC)	P 477.78	P 3,822.23
102(2)	4,681.80	cu.m.	Surplus Common Excavation (roadway & side ditch)	P 183.29	P 858,111.61
103(1)a	142.91	cu.m.	Structure Excavation (Common Soil)	P 294.00	P 42,015.51
103(6)a	24.35	cu.m.	Pipe Culverts and Drain Excavation (Common Soil)	P 294.00	P 7,158.89
104(2)a	2,490.40	cu.m.	Embankment from Roadway Excavation	P 292.65	P 728,805.85
105(1)a	2,304.43	sq.m.	Subgrade Preparation (Common Material)	P 20.33	P 46,843.00
200(1)	835.19	cu.m.	Aggregate Subbase Course, 0.20m.thk. (includes shouldering)	P 1,117.98	P 933,723.91
311(1)c1	2,000.00	sq.m.	Portland Cement Concrete Pavement (Unreinforced) - 0.23m thk, 14 days	P 1,728.74	P 3,457,474.44
500(1)a3	10.00	ln.m.	Pipe Culverts 910 mm dia. , Class II RCPC	P 5,880.00	P 58,800.05
505(2)a	542.38	cu.m.	Grouted Riprap, Class A (Slope Protection)	P 3,902.93	P 2,116,873.83
506(1)	125.43	cu.m.	Stone Masonry (Headwalls, Aprons, Wingwalls, parapets)	P 4,707.93	P 590,516.07
605(1)b1	2.00	each	Warning Signs, (750mm triangle)	P 13,334.17	P 26,668.33
605(6)e2	11.00	each	Hazard Markers (Chevron Signs), 600 x 800mm	P 17,949.80	P 197,447.85
612(1)	96.20	sq.m.	Reflectorized Thermoplastic Pavement Markings - White	P 954.31	P 91,804.37
612(2)	12.00	sq.m.	Reflectorized Thermoplastic Pavement Markings - Yellow	P 978.20	P 11,738.36
624(1)a1	9.00	set	Single Arm Post (6m.), Solar LED Street Light, 50 watts	P 69,356.31	P 624,206.77
SPL	4.00	each	PEO RROW Marker	P 2,700.62	P 10,802.47
TOTAL				P	9,990,262.50

Purpose/Remarks : Furnishing of Labor, Materials and Equipment for the Concreting of Tiguis (Lila) - Cambanse (Loboc) Road, Loboc, Bohol.
 Road I.D. No. : 07BOH 134 - 20%DF - 2022 - 017
 Mode of Procurement : Bidding
 No. of days delivered : 90
 Place of Delivery : Project Site
 To be awarded : By lot

RECEIVED BY: *[Signature]* DATE: 5/25/22
 PROVINCIAL PROCUREMENT MANAGEMENT UNIT
 A-2022-0028
 RSC# _____

Requested By:	Cash Available:	Approved by:
Signature  Printed Name CAMILO L. GASATAN Designation Provincial Engineer	 EUSTAQUIO A. SOCORIN Provincial Treasurer	 ERIGO ARISTOTLE C. AUMENTADO GOVERNOR

PROVINCIAL BUDGET OFFICE
 PROVINCE OF BOHOL
 CONTROL NO. 994 REC'D BY DATE: 5/18/22
 MARK NO. 1412
 VALID UNTIL 12/31/2022
 2021-02-08-93/1072300
 SOURCE: 2021-02-08-201-DF
 PETER ROSS M. R. TOTAL CPA
 FBMO

CHARGED TO: 2021 MF 9: 722
 DATE: 5/17/22