Standard Form Title: Purchase Order

PURCHASE ORDER

GARCIA MEMORIAL PROVINCIAL HOSPITAL, TALIBON, BOHOL
Agency/Procuring Entity

Supplier :	REBOTECH ENGINEERING SERVICES	D.O. No. :	P.O. # - PHO - 2020 - 262
Address :	24 B - Crame St., Nawasa Rd., Brgy. Pasong Tamo, Quezon City	Date :	September 10, 2020
Telephone No.:		Mode of Procurement :	PUBLIC BIDDING
TIN :			

Gentlemen/Mesdames:
Please furnish this Office the following articles subject to the terms and conditions contained herein:

Place of Delivery:	GARCIA MEMORIAL PROVINCIAL HOSPITAL, TALIBON, BOHOL	Delivery Term: Conditions at	Please Read Terms the back hereof
Date of Delivery :	NINETY (90) CALENDAR DAYS AFTER RECEIPT OF NOTICE TO PROCEED	Payment Term: Upon Completion of Delivery	
Warranty Period:	THREE (3) MONTHS		

Item No.	QTY	UNIT	DESCRIPTION OF SUPPLIES	UNIT COST	AMOUNT
					-
1	1	unit	Installation of Pipe-in Oxygen Manual Change Manifold (Gas		-
			Control Unit, Gas Alarm, Outlets and Pipelines)		-
			Supply of Materials, Labor & Equipment for the Pipe-in Oxygen		-
			Manual Change Manifold Using the ff.	498,000.00	498,000.00
			GAS CONTROL UNIT - Installation of 5x5 Oxygen Manual		-
	1	assy.	Change Over Manifold Assembly with Pressure Regulators		-
			and indicators; 2 Oxygen cylinder rack assemblies, header		-
			blocks high pressure pipes and pigtails with oxygen unit	85,000.00	85,000.00
			GAS ALARM - Stand Alone Gas Alarm for Oxygen and		-
	1	assy.	Suction Reset Button Led Lights and Sound for Alarm Trigger		-
			set on Low Pressure	7,500.00	30,000.00
			OUTLET - Oxygen Seal Sealing Wall-Outlet: Chromed Plated		-
	4	units	Gas Outlet in Australian Standard with Customized Wall		-
			Mounted Stainless Steel Plate Cover	45,000.00	180,000.00
			PIPELINE - Main Supply, Distribution and Dropper Lines:		-
	4	units	Copper Pipe Type "1"-seamless, in various size joints brazed		-
			in 45% silver brazing rods isolation valves, hanger/fastener		
			x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x		793,000.00
			TOTAL > > >		VVVVVVVVV

AP JEV No. 2020-12-038891 12-28-2020

(total amount in words) SEVEN HUNDRED NINETY THREE THOUSAND PESOS ONLY

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one (1) percent for everyday of delay shall be imposed.

Very truly yours,

Conforme:

MELVIN J. LARAWAN
REBOTECH ENGINEERING SERVICES
Signature over printed name of Supplier

SEP 23 2020
Date

ATTY. ARTHUR C. YAP
Governor

By Authority of the Governor:

ATTY. KATHYRINE D. PIOQUINTO
Provincial Administrator

101210127 488

Date approved: SEP 17 2020

Funds Available:	Earmarked No. : 1379
EUSTAQUIO A. SOCORIN Provincial Treasurer	Amount : P 797,440.00