

Item No.	Quantity	Unit	Item Description	Estimated Unit Cost	Estimated Amount
1003	250.00	bd.ft.	Batterboard	P 49.00	P 12,248.76
803(1)	21.32	cu.m.	Structural Excavation	P 1,207.50	P 25,743.90
804 (1)	68.00	cu.m.	Embankment	P 783.60	P 53,284.56
900 (1)	23.68	cu.m.	Reinforced Concrete Works	P 7,795.46	P 184,596.51
	3.75	cu.m.	Reinforced Concrete Column Footings		
	3.23	cu.m.	Reinforced Concrete Column		
	2.96	cu.m.	Reinforced Concrete Tie Beam		
	1.78	cu.m.	Reinforced Concrete Roof Beams		
	2.00	cu.m.	Reinforced Concrete Wall Footing and Stiffener Column, Coping and		
	9.96	cu.m.	Reinforced Concrete Ground Floor Slab		
902	2,897.44	kg.	Reinforcing Steel for Concrete Works	P 82.31	P 238,479.70
	312.51	kg.	Reinforcing Steel for Column Footings		
	1,055.28	kg.	Reinforcing Steel for Column		
	742.38	kg.	Reinforcing Steel for Tie Beam		
	390.13	kg.	Reinforcing Steel for Roof Beams		
	120.39	kg.	Reinforcing Steel for Wall Footing and Stiffener Column, Coping and		
	276.75	kg.	Reinforcing Steel for Column Ground Floor Slab		
903	2,520.00	bd.ft.	Forms and Scaffoldings	P 53.43	P 134,650.02
1046	111.41	sq.m.	Masonry Works (CHB Masonry Wall)	P 1,203.52	P 134,083.64
1027	284.00	sq.m.	Cement Plaster Finish	P 184.73	P 52,462.49
1047 (1)	2,595.73	kg.	Roof Framing Works	P 149.84	P 388,948.36
1014	87.00	ln.m.	Pre-Painted Oven Baked Metal Sheets	P 1,205.52	P 104,880.36
1010	17.00	set	Doors and Windows	P 6,723.25	P 114,295.31
			4 set-Door 1, 0.90m x 2.10m, Wooden Panel Door including door jamb		
			2 set - Door 2, 0.60m x 2.10m, Prestige PVC Type Door with Louver		
			1 set-Door 3, Wooden Flush Type Door		
			1 set - Window 1, 1/4 thick Clear Glass 1"x4" Open Back Analok Aluminum Frame, 1.73m x 1.25m		
			2 set-Window 2, 1.80m x 1.20m, Aluminum Frame A-1 Jalousie Window 3/16" x 4' Blades		
			5 set-Window 3, 1.20 x 1.20, Aluminum Frame A-1 Jalousie Window with 3/16 x 4" Blade		
			1 set-Window 4, 1.0x0.9 and 0.20x1.0 Slide with 3/16 Bronze Glass		
			1 set-Window 5, 0.60 x 0.60 Jalousie Aluminum Window		
1003	84.00	sq.m.	Metal Frame & Fiber Cement Board Ceiling	P 1,302.89	P 109,442.97
			48 sq.m. - Interior Ceiling using 4.5mm x 4' x 8' Hardiflex Cement Board on Light Gauga Metal Frame spaced at .60 M.O.C.B.W., using .80m x 12mm x 38m Carrying Channel .40mm x 19mm x 50mm Double Furring on Ceiling Board Joints and 40mm x 19mm x 25mm Single Furring intermediate Joints Light Metal Hangers not to exceed with spacing 1.0m on centers.40 x25mm x 25mm and Gypsum Screw		
			36 sq.m. - Exterior Eave Ceiling Pre-painted Spandrel metal ceiling while on light gauge Metal Studs spaced at .60 M.O.C.B.W., 0.80m x 12mm x 38mm Carrying Channel .40mm x 19mm x 50mm Single Furring Hangers,40mm x 25mm x 25mm Wall angle Gypsum Screw		
			10.53 sq.m. - Double Wall Drywall Partition using 4.5mm x 4' x 8' Hardiflex Cement Board on Light Metal Frame Spaced at 0.60m O.C.B.W.		
			8 pcs. - Wooden Slats .20m x 1.20m Air Ventilation		
1002	1.00	lot	Plumbing Works	P 89,589.36	P 89,589.36
1018 (a)	75.90	sq.m.	Tileworks	P 1,592.33	P 120,858.19
1100	1.00	lot	Electrical	P 156,041.34	P 156,041.34
1032	373.00	sq.m.	Paintings	P 183.62	P 68,490.17
SPL (1)	7.56	cu.m.	Construction of Septic Tank	P 13,312.20	P 100,640.23


**PROVINCIAL BUDGET OFFICE**  
**PROVINCE OF BOHOL**  
 CONTROL NO. 1239 REC'D BY [Signature] DATE [Date]  
 EXPENSE CODE 44284-107400  
 FUND SOURCE [Source]  
 PETER ROSS M. RAUTALAN  
 CONTROLLER


**TOTAL ESTIMATED CONTRACT COST: P 2,088,735.88**


**Purpose/Remarks :** Furnishing of Labor, Materials and Equipment for the **CONSTRUCTION OF TB (DOTS) AT CONG. NATALIO P. CASTILLO MEMORIAL HOSPITAL at Canhangdon Loon, Bohol**

Mode of Procurement : **Bidding**  
 No. of days delivered : **90 Calendar Days**  
 Place of Delivery : **Project Site**  
 To be awarded : **By lot**

Requested By: \_\_\_\_\_ Cash Availability : \_\_\_\_\_ Approved by: \_\_\_\_\_

Signature:   
 Printed Name: **MA. CYRILDA B. TALLO MD**  
 Designation: **Chief of Hospital**

Signature:   
 Printed Name: **EUSTAQUIO A. SOCORIN**  
 Designation: **Provincial Treasurer**

Signature:   
 Printed Name: **HON. ARTHUR C. YAP**  
 Designation: **Governor**