

902 (G)	REINFORCING STEEL FOR STAIR	KGS.	942.10	80.00	75,368.00
900 (H)	REINFORCED CONCRETE SLAB ON GRADE	CU. M.	10.20	7,940.00	80,988.00
90 2(H)	REINFORCING STEEL FOR SLAB ON GRADE	KGS.	339.48	80.00	27,158.40
900(I)	REINFORCED CONCRETE SLAB ON SECOND FLOOR LEVEL	CU. M.	10.44	7,824.00	81,682.56
902(I)	REINFORCING STEEL FOR SECOND FLOOR SLAB LEVEL	KGS.	1,862.00	79.00	147,098.00
903	FORMS, SCAFFOLDINGS AND STAGING	KGS.	3,860.00	54.00	208,440.00
1046 (A)	NEW MASONRY WORKS	SQ. M.	270.86	977.00	264,630.22
1027 (A)	CEMENT PLASTER FINISH FOR CHB IN GROUND AND SECOND FLOOR	SQ. M.	663.00	180.00	119,340.00
1018 (A)	GROUND, SECOND FLOOR AND COMFORT ROOM TILES	SQ. M.	253.68	1,435.00	364,030.80
1018 (B)	TILE FOR STAIRS( 2units )	SQ. M	18.24	2,550.00	46,512.00
1047	ROOF FRAMING AND TRUSSES	KGS.	4,160.79	116.00	482,651.64
1051	STAIR RAILINGS	LENGT H	13.00	5,400.00	70,200.00
1040	ALUMINUM LOUVER	SQ. M	3.34	3,381.00	11,292.54
1032 (A-1)	STEEL PAINTING WORKS	LOT	1.00	42,500.00	42,500.00
1003 (1)E1	INTERIOR CEILING USING METAL FRAME & FIBER CEMENT BOARD CEILING	SQ. M.	189.00	784.00	148,176.00
	4.5mm thick x 1.20m x 2.40m Hardiflex Cement Board on light gauge metal frame spaced at 0.60m on center bothways using 12mm x 38mm carrying channel, 0.40mm x 19mm x 50mm double furring hangers, 0.40mm x 19mm x 50mm single furring hangers and 0.40mm x 25mm x 25mm wall angle				
1003 (1)E2	EXTERIOR CEILING USING SPANDREL ON LIGHT METAL FRAMES	SQ. M.	50.00	1,535.00	76,750.00
	0.40mm x 0.110m x LS metal ceiling board, spandrel (white) using 0.40mm x 0.19mm x 50mm double furring ceiling joist and powder coated, white 0.40mm x 25mm x 25mm wall angle				
	Wooden Slats .20 x 1.20m Air Ventillation with Screen				
1014	PRE- PAINTED OVEN- BAKED METAL SHEETS	SQ. M.	189.60	775.00	146,940.00
1007	WOODEN & PVC DOORS	UNITS	10.00	9,400.00	94,000.00