

Item No.	Quantity	Unit	Description	Rate	Amount	Unit	Amount
A.2	1.00	lot	PERMITS & CLEARANCES Application and Processing of Building Permit with the Office of the Building Official	5,250.00	P	5,250.00	5,250.00
A.3	1.00	lot	PROJECT BILLBOARD (4'x 8') (TARPAULIN W/ STANDARD SAFETY AND HEALTH	9,061.97	P	9,061.97	9,061.97
A.4	1.00	lot	SAFETY AND HEALTH	2,092.99	P	2,092.99	2,092.99
PART B	EARTHWORKS						
800(1)	140.40	sq.m.	CLEARING AND GRUBBING	18.16	P	2,549.66	2,549.66
803(1)	36.35	cu.m.	STRUCTURAL EXCAVATION	1,388.26	P	50,463.07	50,463.07
SPL-1	120.00	bd.ft.	BATTERBOARD	51.38	P	6,165.93	6,165.93
804 (1)	130.00	cu.m.	EMBANKMENT	699.71	P	90,962.34	90,962.34
PART C	STRUCTURAL WORKS						
900 (1)	3.75	cu.m.	REINFORCED CONCRETE FOR COLUMN FOOTING	8,819.35	P	33,072.56	33,072.56
902 (1)	331.45	kgs.	REINFORCING STEEL FOR COLUMN FOOTING	84.45	P	27,991.95	27,991.95
900 (1)	3.00	cu.m.	REINFORCED CONCRETE FOR FOOTING TIE BEAM	8,748.12	P	26,244.37	26,244.37
902 (1)	755.050	kgs.	REINFORCING STEEL FOR FOOTING TIE BEAM	85.40	P	64,480.96	64,480.96
900 (1)	4.86	cu.m.	REINFORCED CONCRETE COLUMN	9,265.90	P	45,032.29	45,032.29
902 (1)	1,889.190	kgs.	REINFORCING STEEL FOR COLUMN	84.18	P	159,026.82	159,026.82
900 (1)	3.17	cu.m.	REINFORCED CONCRETE FOR ROOF BEAMS	9,163.41	P	29,048.02	29,048.02
902 (1)	727.080	kgs.	REINFORCING STEEL FOR ROOF BEAMS	84.92	P	61,743.90	61,743.90
900 (1)	7.05	cu.m.	REINFORCED CONCRETE FOR SLAB ON FILL	8,547.35	P	60,258.81	60,258.81
902 (1)	247.230	kgs.	REINFORCING STEEL FOR SLAB ON FILL	84.49	P	20,888.11	20,888.11
900 (1)	1.67	cu.m.	REINFORCED CONCRETE WALL FOOTING AND WALL STIFFENER	10,422.10	P	17,404.92	17,404.92
902 (1)	238.92	kgs.	REINFORCING STEEL FOR WALL FOOTING AND WALL STIFFENER	83.53	P	19,956.70	19,956.70
900 (1)	0.86	cu.m.	REINFORCED CONCRETE LINTEL BEAM AND CONCRETE COPING	10,221.41	P	8,790.41	8,790.41
902 (1)	144.42	kgs.	REINFORCING STEEL FOR LINTEL BEAM AND CONCRETE COPING	88.25	P	12,745.43	12,745.43
903	3,424.00	bd.ft.	FORMS and SCAFFOLDINGS	55.40	P	189,696.71	189,696.71
1047	2,679.07	kgs.	STRUCTURAL STEEL (ROOF FRAMING, FASCIA & RAMP RAILING)	173.23	P	464,090.90	464,090.90
PART D	ARCHITECTURAL WORKS						
1046	240.21	sq.m.	MASONRY WORKS (6" CHB for Exterior and 4" for Interior Wall)	1,310.42	P	314,775.97	314,775.97
1027 (1)	363.00	sq.m.	CEMENT PLASTER FINISH	193.70	P	70,311.96	70,311.96
1018	65.59	sq.m.	CERAMIC/GRANITE TILES (COMFORT ROOMS)	1,880.09	P	123,307.76	123,307.76
1003 (1)a	85.28	sq.m.	4.5MM THK FIBER CEMENT BOARD ON LIGHT METAL FRAME	889.13	P	75,824.99	75,824.99
1009 (1)a	7.56	sq.m.	Supply and installation of 4.5mm thk Fiber Cement Board ceiling on 0.40mm x 19mm x 50mm double furring, ceiling joist spaced at 0.60m bothways including pre-fab wooden angles				
1010 (2)c	8.82	sq.m.	JALOUSIE GLASS WINDOW				
		sq.m.	GLASS DOORS				
			Supply and installation of glass doors: 2 units - D-1: 1.6mWx2.1mL Double swing, double throw glass door with 1/4" thk tempered glass in two panels on analog (brown) aluminum frame with transom 1 unit - D-2: 1.0mWx2.1mL Double swing, double throw glass door with 1/4" thk tempered glass in two panels on analog (brown) aluminum frame with transom				
1010(2)b	1.00	set	WOODEN DOORS W/ DOOR JAMB	11,810.87	P	11,810.87	11,810.87
1043(2)	1.00	set	PVC DOORS AND FRAME FOR C.R.	4,769.42	P	4,769.42	4,769.42
1032 (1)a	372.58	sq.m.	MASONRY PAINTING (INCLUDING FIBER CEMENT BOARD)	237.20	P	88,374.42	88,374.42
1032 (1)b	4.74	sq.m.	WOODEN PAINTING (Wood Doors)	432.67	P	2,050.86	2,050.86
PART E	ROOFING WORKS						
1014(1)b2	119.00	ln.m.	PRE - PAINTED METAL SHEETS				
PART F	ELECTRICAL WORKS						
1100	1.00	lot	CONDUIT, BOXES AND FITTINGS	1,274.98	P	151,722.08	151,722.08
1101	1.00	lot	WIRES AND WIRING DEVICES	19,880.94	P	19,880.94	19,880.94
1102	1.00	lot	PANEL BOARD	69,660.70	P	69,660.70	69,660.70
1103	1.00	lot	LIGHTING FIXTURES	11,612.32	P	11,612.32	11,612.32
PART G	AIR-CONDITIONING UNITS AND EXHAUST FAN						
1200	1.00	lot	AIR-CONDITION UNITS AND EXHAUST FAN	38,625.73	P	38,625.73	38,625.73
			Supply of 3/4 HP A/C Unit window type including bracket installation; supply and installation of wall mounted exhaust fan				
PART H	PLUMBING WORKS						
1002	1.00	lot	PLUMBING (SANITARY LINES, WATERLINES, & FIXTURES):	27,055.98	P	27,055.98	27,055.98
PART I	CONSTRUCTION OF SEPTIC TANK						
SPL (1)	11.29	cu.m.	SEPTIC TANK	5,749.36	P	64,910.29	64,910.29

CENTRAL BUDGET OFFICE
PROVINCE OF BOHOL
OFFICE OF THE PROVINCIAL TREASURER

4-394-31
13,029-20

2980 / 44220 A-10704010

VALID UNTIL 12/31/21
AMOUNT 2,654,680.92

PETER LESM. R. TALLO, CPA

TOTAL ESTIMATED CONTRACT COST: P / 2,654,680.92


Purpose/Remarks: Furnishing of Labor, Materials and Equipment for the CONSTRUCTION OF CADAVER HOLDING AT CONG. NATALIO P. CASTILLO SR. MEMORIAL HOSPITAL at Canhangdon, Loon Bohol

Mode of Procurement: Bidding


No. of days delivered: 90 Calendar Days


Place of Delivery: Project Site

To be awarded: By lot

Requested By:  MA. CYRILDA S. TALLO M.D.
Chief of Hospital

Cash Availability:

Approved by:  EUSTACIO A. SOCORIN
Provincial Treasurer

 HON. ARTHUR C. YAP
Governor

DATE: 9/3/21
2,654,680.92