

			<p>2 sets - Window 1 ,Open-back Powdered Coated,Green,Aluminum Frame,Four Glass Panel Frame using ¼" thk., Glass fixed Awning Window 1, (2.4m x 2.00m )</p> <p>2 sets - Window 2 - Open-back Powdered Coated,Green,Aluminum Frame,Four Glass Panel Frame using ¼" thk., Glass fixed Sliding Window 2, (1.5m x 2.80m )</p> <p>2 sets - Window 3- Open-back Powder Coated ,Green Aluminum Frame with Transom,Three Glass Panel Frame using ¼" thk., Tempered Glass Sliding Window ( 1.5m x 2.10m )</p> <p>2 sets - Window 4 - Open-back Powder Coated (green ) Aluminum Frame with Transom, Single Glass Panel Frame using ¼" thk. Tempered Glass Sliding Window (1.5m x 1.40m)</p> <p>1 set - Window 5 - Open-back Powder Coated (green ) Aluminum Frame with Transom single Glass Panel Frame using ¼" thk. Tempered Glass Sliding Window (1.20m x 1.40m)</p> <p>2 sets - Window 6, 0.60m x 2.10m, Open-back Powder Coated,Green, Aluminum Frame,Three Glass Panel Frame</p> <p>6 sets - Window 7, 0.60m x 1.40m,Open-back Powder Coated,Green, Aluminum Frame,Two Glass Panel Frame,using ¼" thk., Tempered Glass,Sliding Window</p> <p>1 set - Window 8,0.60m x 0.70m, Open-back Powder Coated,Green, Aluminum Frame,Two Glass Panel Frame,using ¼" thk., Tempered Glass, Awning Window</p>					
1100 1200(13)	1.00 7.00	lot sets	<p>Electrical Pipe, Wires and Fixtures</p> <p>AIRCONDITIONING - SPLIT TYPE WALL MOUNTED FULL DC INVERTER</p> <p>Supply and Installation of:</p> <p>5 sets - Hitachi Royal 3-in-1 Split Type Wall Mounted Full DC Inverter Airconditioning Unit, 1.5 HP,power savings of up to 65%, equipped with anti-mold and cleaning function that purifies the air by eliminating molds and bad odors after you turn the unit on and off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230V, 1ph,60hz, Model RAS-15HT/RAC-15HTP, 230V/1ph/60hz. Compressor warranty:5 years, including support, drains, circuit breakers, wires, tapes and other accessories. For Isolation Rooms</p> <p>1 set - Hitachi Royal 3-in-1 Split Type Wall Mounted Full DC Inverter Airconditioning Unit, 0.80HP,power savings of up to 65%, equipped with anti-mold and cleaning function that purifies the air by eliminating molds and bad odors after you turn the unit on and off, also equipped with Nano Silver and Photocatalyst filter and PM2.5 filter, wireless remote, 230V, 1ph,60hz, Model RAS-08HT/RAC-08HTP, 230V/1ph/60hz. Compressor warranty:5 years, including support, drains, circuit breakers, wires, tapes and other accessories. For Treatment Room.</p> <p>1 set - Airconditioning Unit, 4.0HP,nominal cooling capacity of 11.2 kw (38,216 Btu/hr.), ceiling cassette, Full DC Inverter Technology (Inverter Compressor, Inverter Module, and Inverter Fan Motor), equipped with overvoltage protection relay that protects the unit from damage caused by overvoltage, Japan made high efficiency scroll compressor, wired remote controller. PROPOSED BRAND: HITACHI UTOPIA IVX A/C, 4-way ceiling cassette indoor unit, Model RCI-4.0 FSN1Q/RAC-112SQB, 230V/1ph/60hz. including support, drains, circuit breakers, wires, tapes and other accessories. For Nurse Station, Waiting Area and Lobby</p>	P P	551,624.26 101,133.70	P P	551,624.26 707,935.90	
1200 (14)	3.00	sets	<p>VENTILATOR</p> <p>Supply and Installation of:</p> <p>1 set - ENERGY RECOVERY VENTILATOR, 2,000 cu.m. per hr. airflow, motor output : 200 x 4 watts, HITACHI Model KPI-2002Z, 220V, 1ph, 60hz, including accessories</p> <p>1 set - ENERGY RECOVERY VENTILATOR, 1,500 cu.m. per hr. airflow, motor output : 200 x 4 watts, HITACHI Model KPI-1502Z, 220V, 1ph, 60hz including accessories</p> <p>1 set - ENERGY RECOVERY VENTILATOR, 1,000 cu.m. per hr. airflow, motor output : 200 x 2 watts, HITACHI Model KPI-1002Z, 220V, 1ph, 60hz including accessories</p>	P	621,281.06	P	1,863,843.19	
1208	1.00	lot	FIRE ALARM SYSTEM	P	105,184.65	P	105,184.65	
1002 (4)	1.00	lot	SANITARY PIPES AND FITTINGS	P	133,530.78	P	133,530.78	
1002.2.4	2.00	units	SEPTIC TANK, 3.6 x 1.6m x 2.15 = 12.36 cu.m.	P	78,768.52	P	157,537.03	
1003	1.00	units	CARPENTRY WORKS FOR COUNTER TABLE	P	25,121.14	P	25,121.14	
1032 (a)	897.72	sq.m.	PAINTING WORKS ON NEW MASONRY	P	205.45	P	184,438.06	
1032 (b)	236.80	sq.m.	PAINTING WORKS OF CEILING	P	203.13	P	48,100.52	
			XXXXXXXXXX					
<b>TOTAL ESTIMATED CONTRACT COST:</b>							<b>P</b>	<b>10,386,831.36</b>