

902 (i)	REINFORCING STEEL FOR WALL STIFFENER	KG.	247.63	83.10	20,578.05
903	FORMS AND SCAFFOLDINGS	BD.FT	8,998.00	46.76	420,746.48
PART E	MASONRY WORKS				-
506 (1)a	EXTERIOR MASONRY WORKS	SQ.M.	232.96	670.63	156,229.96
506 (1)b	INTERIOR MASONRY WORKS	SQ.M.	205.95	453.97	93,495.12
PART F	FINISHING				-
1027	CEMENT PLASTER FINISH	SQ.M.	970.28	141.21	137,013.24
PART G	TILEWORKS				-
1018 (a)	FLOORING GRANITE TILES	SQ.M.	286.65	1,052.35	301,656.13
1018 (b)	COMFORT ROOM CERAMIC TILES	SQ.M.	48.20	839.65	40,471.13
1018 (c)	COUNTER GRANITE SLAB	SQ.M.	8.64	3,113.54	26,900.99
PART H	METAL STRUCTURES				-
403 (a)	ROOF FRAMING AND TRUSSES				-
a.	MAIN BUILDING	KG.	10,793.292	102.50	1,106,312.43
b.	CANOPY	PC.	41.00	1,298.66	53,245.06
c.	STAINLESS RAILINGS	PC.	5.00	25,508.00	127,540.00
d.	GRABRAIL FOR PWD COMFORT ROOM	SET	2.00	7,941.00	15,882.00
1032(a-1)	STEEL PAINTING WORKS	LOT	1.00	7,774.00	7,774.00
403 (b)	FIBER CEMENT BOARD AND LIGHT METAL FRAME WORKS	SQ.M.	415.11	1,180.63	490,091.32
	Supply of Materials, Labor, and Equipment for Fiber Cement Board Ceiling & Drywall, & Spandrel				-
	6mm x 4' x 8' Hardiflex Cement Board on light gauge metal ceiling joist spaced at 0.60m on center bothways using 0.80mm x 12mm x 38mm carrying channel, 0.40mm x 19mm x 50mm double furring on ceiling board joists, 0.40mm x 19mm x 25mm single furring hangers and 0.40mm x 25mm x 25mm wall angle, interior ceiling	SQ.M.	283.00		
	12mm x 4' x 8' Hardiflex Cement Board, double wall on light gauge vertical & horizontal wall studs using 0.40mm x 50mm x 100mm rectangular tube spaced at 0.60m on center both ways, drywall partition		56.28		