

NEMA 12 ENCLOSURE GA.14 POWDER COATED PAINT.

- * (2) units Draw-out Type Electrically Operated Circuit Breaker 2500AT/3200AF 3P 240V 60Hz
- * (1) unit Mechanical Interlock Cable Type
- * (1) unit Automatic Transfer Switch (ATS) Controller with battery charger complete with over/under voltage relay, frequency and phase sequence
- * (2) units molded case breaker (MCB) 6AT 3P
- * (2) units molded case breaker (MCB) 10AT 3P
- * (1) unit molded case breaker (MCB) 6AT 2P
- * (1) unit magnetic contactor realy 2NO/2NC
- * (1) unit relay 4P, DT, 230V
- * (3) units current transformer 2500;5A

IX 1 lot

SUPPLY DELIVERY AND INSTALLATION OF ADDITIONAL CRIMPING TYPE TERMINAL LUGS FOR EXISTING AUTOMATIC TRANSFER SWITCH (ATS)

- * (4) sets of 3-250mm2 (Emergency Side- Genset Circuit Breaker)
- * (4) sets of 3-250mm2 (Common Side- LVSG)

X 1 lot

SUPPLY DELIVERY AND INSTALLATION OF NEW POWER CABLES (GENERATOR- ATS EMERGENCY SIDE)

- * (4) sets of 3-250mm2 THHN Wire
- * (1) set of 60mm2 THHN Wire
- * (1) set Control wire for automatic switching of Genset and Automatic Transfer Switch (ATS)

XI 1 lot

SUPPLY DELIVERY AND INSTALLATION OF NEW POWER CABLES (ATS COMMON SIDE- LVSG)

- * (4) sets of 3-250mm2 THHN Wire
- * (1) set of 60mm2 THHN Wire

XII 1 lot

SUPPLY DELIVERY AND INSTALLATION OF NEW MECHANICAL VENTILATION

- * New Detachable Louver (Entrance)
- * Hi-heat paint and insulated exhaust tail pipe includes flapper and supports
- * Extended Radiator Duct
- * Fresh Intake Air Duct

XIII 1 lot

LOAD BANK TEST (MAX 2HRS BUILDING LOAD ONLY)

XIV 1 lot

TRAINING ORIENTATION ON THE OPERATION AND BASIC MAINTENANCE

NOTE:

- * BIDDERS MUST HAVE A VALID (OEM) MANUFACTURER'S DISTRIBUTORSHIP CERTIFICATE
- * MANUFACTURER'S MUST HAVE SOLE DISTRIBUTORSHIP WITH RED RIBBON & CONSULAR AUTHENTICATION REPRESENTING THE BIDDER
- * MANUFACTURER'S MUST HAVE QUALITY MANAGEMENT SYSTEM ISO 9001: 2008 REPRESENTING THE BIDDER
- * MANUFACTURER'S MUST HAVE ENVIRONMENTAL MANAGEMENT SYSTEM ISO 14001 REPRESENTING THE BIDDER
- * BIDDERS MUST HAVE BRANCH OFFICE IN BOHOL
- * BIDDERS MUST HAVE EMPLOYED STANDBY TECHNICIAN IN BOHOL
- * BIDDERS MUST HAVE ACTIVE AND EXISTENSE FOR 15 YEARS IN CONSTRUCTION INDUSTRY WITH PROOF OF VALID SEC CERTIFICATE.

RECEIVED BY: *[Signature]* DATE: 10/1/2022
 PROVINCIAL PROJECT MANAGEMENT UNIT
 NO. 8620-2202-2022
 UNIT: 19,400.00 SC# 589
 CKAS TO APP

PROVINCIAL BUDGET OFFICE
PROVINCE OF BOHOL

EXPENSE ACCOUNT
2021-030R 20/1/DF

9909/9000-01-01-01/1073050 P 19,400,000.00

12/31/2022

0589

RECEIVED

12/31/2022

11/15/2022

TOTAL ESTIMATED CONTRACT COST: P 19,400,000.00

Purpose/Remarks : Supply, Delivery, Installation and Commissioning of One (1) Unit Brand New Generator Set, Pull-out and Transfer of existing Genset Unit and Rehabilitation of Mechanical Ventilation System for Genset Room

Mode of Procurement : **Bidding**

Duration Date : **90 Calendar days**

Place of Delivery : **New Capitol Site, Cogon District, Tagbilaran City, Bohol**

Requested by:	Cash Availability	Approved by:
<i>[Signature]</i> GLICERIO P. DOLORITOS, Ph. D. Department Head	<i>[Signature]</i> EUSTAQUIO A. SOCORIN Provincial Treasurer	<i>[Signature]</i> HON. ERICO ARISTOTLE C. AUMENTADO Governor