| - | | | W | PR No | | Done | June 25, 2021 |
|--------------------------------|---------|------|--|---------------------|--------------|------------------|---------------|
| Section : SAI No | | | | | | | |
| | | | | | ALOBS NO. | | Date : |
| Item No. | Quantiy | Unit | Item Description | Estimated Unit Cost | | Estimated Amount | |
| Item No. | | | | 5 | 161 177 60 | D | 161,122.5 |
| L | 1.00 | lot | GENERAL REQUIREMENTS Mobilization and De-mobilization Licensing and Permits Site Management and Ceiling Repairs and Other on Site Repairs | P | 161,122.50 | | |
| П. | 1.00 | lot | PUMPS AND ACCESSORIES (SPRINKLER SYSTEM) 1 set - FirePump Split Case Horizontal 50 hp, 100 psi, 500 gpm, 3 phase 230VAC and Jockey Pump Vertical Multi Stage 3 hp, 100 psi, 30 gpm, 3phase 230VAC with Motor Controller 1 pc - Alarm Check Valve Assembly 100mm 1 pc Fire Department Connection 100mm x 65mm 8 sets - Fire Hose Cabinet 100 ft. 8 pcs OS & Y Gate Valve 100mm 4 pcs OS & Y Gate Valve 100mm w/ Supervisory 4 pcs Waterflow Switch 100mm System Sensor Brand | P | 1,562,746.50 | P | 1,562,746.5 |
| ш. | 1.00 | lot | 4 pcs Drain Valve Assembly Sight Glass 25mm B.I. PIPES AND FITTINGS 24 length - 100mm x 20ft. Schedule 40 28 length - 75mm x 20ft. Schedule 40 19 length - 65mm x 20ft. Schedule 40 22 length - 50mm x 20ft. Schedule 40 17 length - 40mm x 20ft. Schedule 40 83 length - 25mm x 20ft. Schedule 40 Assorted Threaded and Welded Fittings: Elbow, Tee's,Reducers, | P | 1,074,777.64 | P | 1,074,777.6 |
| IV. | 1.00 | lot | Flange and Others CONSUMABLES / MISCELLANEOUS Bracket and Supports, Clips and Pipe Hangers, PVC Pipes and Angle Bars, Tapelon, Welding Rods, Epoxy Primer Paint Red Oxide, Epoxy Tope Gloss Int'l Red, Cutting Disk and Stones, Screw and Toxs Paint Brush and Others | P | 162,746.85 | Р | 162,746.8 |
| v. | 1.00 | lot | LABOR, SUPERVISION, TESTING AND COMMISSIONING | Р | 717,255.00 | Р | 717,255.0 |
| TOTAL ESTIMATED CONTRACT COST: | | | | | | P | 3,678,648.4 |

at Catigbian, Bohol

Mode of Procurement: Bidding

No. of days delivered: 75 Calendar Days

Place of Delivery:

Project Site

To be awarded:

By lot

Requested By:

Cash Availability:

Approved by:

Signature

Printed Name

NORANGEL M. CARREON, M.D.

Designation

Chief of Hospital

Cash Availability:

Approved by:

HON. ARTHUR C. YAP

Governor

A-3811 DDS DQ3

B31678 648 49

Sm. On the state of the st

PHOVINCIAL BUDGET OFFICE
PROVINCE OF ROAD
PROVINCE OF ROAD
PROVINCE OF ROAD
PROVINCE OF ROAD
PARENTE OF ROAD
P

PETER DESM RETURNICH