

F-PRMCOORAPUS-2017-653
4/21/23

Department: Governor's Office

PR No. _____
SAI No. _____
ALOBS No. _____

Date: March 30, 2023
Date: _____
Date: _____

Section: TD 3/M

Item No.	Quantity	Units of Issue	Item Description	Estimated Unit Cost	Estimated Cost
1	1	set	PREMIER INVERTER SPLIT TYPE WALL MOUNTED A/C 2.0hp, DC compressor, 3D airflow, cooling capacity: 12,000BTU/hr, 60% savings o power consumption, Wireless remote control, 12 grades indoor fan speed, 3D airflow, double level air laps, 1 watt power standby, Refrigerant used = R32, equipped with self-diagnosis function and refreshed air function fro cleaner and fresher air, equipped with digital display sensor that disolays error codes, fast cooling, auto-restart, timer switch, also equipped with standard high density filters for dust and other elemnts for cleaner and healthier air, built in louver memory function	54,088.00	54,088.00
			INSTALLATION MATERIALS FOR A/C EQUIPMENT SUPPORT, DRAINS, CIRCUIT BREAKERS, WIRES, & OTHER ACCESSORIES		
2	1	pcs	Service Circuit Breaker. 20A		
3	4	mts	#10 AWG THHN (outdoor unit to breaker)	790.00	790.00
4	8	mts	Royal cord, 4x#14	50.00	200.00
5	1	lghts	PVC Pipe Blue, 3/4" dia. (for drain line)	120.00	960.00
6	2	pc	PVC Elbow, blue, 3/4"	135.00	135.00
7	6	set	Expansion Shield with lag screw	25.00	50.00
8	1	pcs	Silver Rod	130.00	780.00
9	4	pcs	Bolts, nuts and washers	89.00	89.00
10	1	lghts	Angular Bar 11/2" x 11/2" x3/16" x20'	20.00	80.00
11	1	lot	Other accessories (Paint, clips, tapes, fittings, etc.)	1200.00	1,200.00
			AIRCON PIPING SYSTEM		
12	25	ft	1/2" dia. Refrigerant pipe, soft drawn	750.00	750.00
13	25	ft	1/4" dia. Refrigerant pipe, soft drawn	85.00	2,125.00
14	5	lghts	1/2" x 3/4" x 6' rubber insulation Superlon	55.00	1,375.00
15	5	lghts	1/4" x 3/8 x 6' rubber insulation Superlon	200.00	1,000.00
16	0.5	roll	Polyethylene Tape	90.00	450.00
17	2	pcs	Copper elbows, 1/2"	800.00	400.00
18	2	pcs	Copper elbows, 1/4"	40.00	80.00
19	0.5	tnk	Nitrogen	30.00	60.00
20	1	tnk	Mapp Gas	1200.00	600.00
21	0.5	tnk	Refrigerant R32	850.00	850.00
22	1	lot	Other accessories (Paint, hangers, supports, clips, sleeves etc.)	6890.00	3,445.00
			LABOR COST (Installation, wall chipping, bracket fabrication minor masonry works & Test n Comssioning)	1000.00	1,000.00
			LABOR COST (Installation, wall chipping, bracket fabrication minor masonry works & Test n Comssioning)	5400.00	5,400.00
			Place of Delivery: Governor's Office / MOU(Botika sa Kapitolyo) Period of Delivery: 5 Days Upon Receipt of NTP/PO Mode of Procurement: Alternative Mode of Procurement		
			TOTAL:		75,907.00

PROVINCIAL BUDGET OFFICE
PROVINCE OF BOND
CONTROL NO. 714
RECORD NO. 120A
EXPENSE CODE 100-01-1070020
FUND SOURCE 2022-019
PETER ROSS
DATE 3/31/23
VALID UNTIL 11/30/23
AMOUNT 75,907.00
DATE 01/21/20

2023-0182
2023-0182
4/14/23

Purpose: Storage of Medical Supplies at the Office of Medical Outreach Unit (Botika sa Kapitolyo)

Requested by:	Cash Availability:	Approved by:
		ERICO ARISTOTLE C. AUMENTADO
Printed Name: CAROLINE FAME P. HINAY	EUSTAQUIO A. SOCORIN	Governor
Designation: Supervising Administrative Officer	Provincial Treasurer	By Authority of the Governor:
		ASTERIA C. CABERTE
		Provincial Administrator